

FIRST FLOOR KEY PLAN
NO SCALE

	PLUMBING SYMBOLS &	<b>ABBREVIATIONS</b>	LIST	
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	
	SANITARY, S.	9	BALANCING VALVE	
	VENTPIPE, V.			
	COLD WATER, CW		REMOVE FROM EXISTING	
нw ————	HOT WATER	•	CONNECT TO EXISTING	
HWR	HOT WATER RETURN		DIDE UD	
——G——	GAS PIPING	•	PIPE UP	
<del></del>	CHECK VALVE	<del></del>	PIPE DOWN	
	BALANCING VALVE	<del></del>	PIPE CAP	
——	UNION	ε	BOTTOM CONNECTION	
Mai a lass	THERMOMETER	×	PIPE ANCHOR	
<u></u>	PRESSURE GAUGE WITH SNUBBER		LINE BREAK	
<del></del>	SHUTOFF VALVE			
<del></del>	STRAINER			
	BUTTERFLY VALVE			
<del></del>	SOLENOID VALVE			
	FLOW METER FITTING			
	PRESSURE REDUCING VALVE			
——CD——	CLEARWATER OR CONDENSATE DRAIN			
	BACKFLOW PREVENTER			
——₩——	GLOBE VALVE	STATES 1	STATES TYPE OF SYSTEM.	
~~	PIPING FLOW DIRECTION			
C.O. F.C.O.	CLEAN-OUT C.O. FLUSH WITH FINISHED FLOOR	PLUMBING	EQUIPMENT DESIGNAT	
A.F.F.	ABOVE FINISH FLOOR			
TYP	TYPICAL		STATES NUMBER OR LETTER	
GPM	GALLONS PER MINUTE	CORRESP	PONDING TO RELATED SCHEDUL	
	PLAN NOTE REFERENCE SYMBOL			
(A)	PLAN NOTE REFERENCE STMBUL			

## GENERAL REQUIREMENTS

- 1. REFER TO THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS OF THIS PROJECT.
- 2. BID PHASE:
  IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW ALL DOCUMENTS TO INCLUDE PLANS AND SPECIFICATIONS FOR THE ARCHITECTURAL AND OTHER WORK UNDER OTHER DIVISIONS THAT CAN AFFECT THE WORK OF THIS DIVISION. THE CONTRACTOR SHALL ISSUE A FORMAL REQUEST FOR INFORMATION FOR CLARIFICATIONS OF ANY DISCREPANCIES IN THE DOCUMENTS PRIOR TO FINAL BID SUBMISSION.
- PRE-CONSTRUCTION:
  IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW ALL REVISED DOCUMENTS TO INCLUDE ARCHITECTURAL PLANS AND WORK UNDER OTHER DIVISIONS THAT CAN AFFECT THE WORK OF THIS DIVISION. THIS INCLUDES REVIEW OF ALL ADDENDUMS, REVISIONS AND SHOP DRAWINGS THAT AFFECT THE WORK OF THIS DIVISION. THE CONTRACTOR SHALL NOTIFY THE A/E TEAM OF ANY DISCREPANCIES PRIOR TO FINAL ROUGH—IN.

## SPECIAL CONDITIONS

- A. DEMOLITION COORDINATION:
- REFER TO ARCHITECTURAL DEMOLITION PLANS FOR ADDITIONAL DEMOLITION REQUIREMENTS.
- REFER TO ARCHITECTURAL PLANS AND/OR SUPPLEMENTAL DOCUMENTS FOR CONSTRUCTION PHASE SEQUENCE REQUIREMENTS FOR OCCUPIED SPACES AFFECTED BY THE WORK.
- 3. NOTIFY THE LANDLORD OF ANY WORK THAT MAY DISRUPT OTHER AREAS OUTSIDE OF THE WORK AREA.
- B. **EQUIPMENT COORDINATION:**
- 1. REFER TO ARCHITECTURAL EQUIPMENT PLANS, FURNITURE PLANS, ELEVATIONS, CASEWORK ELEVATIONS AND OTHER RELATED PLANS FOR ADDITIONAL MEP
- C. EXISTING SANITARY WORK:
- CONTRACTOR SHALL VERIFY LOCATION OF EXISTING SANITARY MAINS, SIZES, AND CLEANOUTS IN THE AREA OF NEW PLUMBING WORK.
- VERIFY LOCATION OF NEW TIE IN POINTS TO THE MAIN SANITARY LINE. VERIFICATION WILL INCLUDE DIGGING NECESSARY TEST PITS TO VERIFY LOCATION AND APPROPRIATE DEPTH PRIOR TO COMMENCEMENT OF THE WORK AND TRENCHING NEW LINES.
- 3. CONTRACTOR SHALL CONFIRM MAIN LINES ARE CLEAR OF DEBRIS AND FREE FLOWING PRIOR TO TIE—IN WORK.
- CONTRACTOR SHALL PROVIDE AN AS BUILT SKETCH OF THE EXISTING LINES CONFIRMING INVERTS, SIZES, AND DIRECTION OF FALL.



HOFMANN ASSOCIATES, INC. 606 Baltimore Ave.

Suite 102 Towson, Maryland 21204 410.828.9090 fax 410.828.4433



CHESAPEAKE MEDICAL IMAGING


CHESAPEAKE MEDICA
1312 BELLONA AVE., SUITE 102
LUTHERVILLE, MD. 21093

ISSUE DATE

1			
ı			
		4.400.000.00	
		3030-300	

THE CONCEPTS, IDEAS, DESIGNS
AND IMAGES ARE INTENDED ONLY
FOR THE PROJECT SPECIFIED ON
THIS SHEET AND ARE THE SOLE
PROPERTY OF HOFMANN
ASSOCIATES, INC. THEY ARE NOT TO
BE REPRODUCED OR USED BY
OTHERS WITHOUT WRITTEN
PERMISSION BY HOFMANN
ASSOCIATES, INC.

COVERSHEET



PROGRESS ISSUE 11-11-2014

MEP Consulting Engineers since 1959

757 Frederick Road Suite 300 - Catonsville, Maryland 21228
Phone. 410'869-7282 Web: www.SRBRengineers.com
SRBR No: 14128

project no. : 14-080