FINISH SCHEDULE

ROOM #	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS SOUTH	WALLS EAST	WALLS WEST	DOORS	TRIM	BULK.	CEILING	SPECIAL CONDITIONS
GROUND FLOOR												
608	EX. DRY STORAGE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
612	CLOSET	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
619	MDS / DIET / OFFICE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
620	EVS OFFICE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
622	EXPANDED BEAUTY SHOPPE	VCT	VB	P1	P1	P1	P1	P	P	P	ACT II	
623	ELEC / TELE	SG	VB2	P1	P1	P1	P1	P	P		P	
625	MECH	SG	VB2	P1	P1	P1	P1	P	P		P	
626	OFFICE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
627	CENTRAL SUPPLY	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
628	CENTRAL SUPPLY	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
629	JANITOR	VCT4	VB2	P1	P1	P1	P1	P	P		P	
630	HOUSEKEEPING / SUPPLIES	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
631	MAINTENANCE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
632	MECH	SG	VB2	P1	P1	P1	P1	P	P		P	
633	STAIR #3	VCT4	VB2	P1	P1	P1	P1	P	P		P	
635	NEW DRY STORAGE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
636	WHEELCHAIR STORAGE	LVT	VB	P	P	P	P	P	P		ACT II	
637	DINING WAITING	LVT	VB	P	P	P	P	P	P		ACT II	
638	DINING ROOM	G	WB / P	P	P	P	P	P	P	P	ACT III	
638A	BAR	VCT								P	ACT V	FLOORING IS SAFETY FLOORING
639	SERVING PANTRY	VCT	VB	FRP	FRP	FRP	FRP	P	P		ACT III	FLOORING IS SAFETY FLOORING
640	PUBLIC TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	P	P		ACT I	
641	PUBLIC TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	P	P		ACT I	
642	GAME ROOM	G	VB	P	VWG	P	P	P	P		ACT I	
643	NEW CONFERENCE	G	VB	VWG	VWG	VWG	VWG	P	P		ACT II	
644	NEW THEATER	G	WB / P	P*	P*	P*	P*	P	P		ACT I	P* W/ FABRIC INSERTS
645	A / V STORAGE	G	VB	P	P	P	P	P	P		ACT I	
646	STORAGE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
647	EX. SOUTH STAIR										P	
648	LOUNGE	LVT	VB	P	P	P	P	P	P		ACT II	
649	ELEVATOR LOBBY	LVT	VB	P	P	P	P	P	P	P	ACT II	
650	CHAPEL	G	VB	VWG	VWG	VWG	VWG	P	P		ACT I	
651	ACTIVITY DIRECTOR	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
652	HUMAN RESOURCES	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
653	STORAGE	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
654	MEDICAL RECORDS	VCT4	VB2	P1	P1	P1	P1	P	P		ACT I	
655	RESIDENT LAUNDRY	VCT	VB	P	P	P	P	P	P		ACT I	
656	PET ROOM	CT	CTB	P	CT	P	P	P	P		ACT I	
657	JANITOR	VCT4	VB2	P1	P1	P1	P1	P	P		P	
658	PUBLIC TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	P	P		ACT I	
659	MECH	SG	VB2	P1	P1	P1	P1	P	P		P	
660	LOUNGE	G / LVT	VB	P	P	P	P	P	P	P	ACT II	
661	ELEC / TELE	SG	VB2	P1	P1	P1	P1	P	P		P	
667	STAIR #4	VCT4*	VB2	P1	P1	P1	P1	P	P		P	*VCT4 LANDINGS ONLY, PANS AND RAILS P4A
668	A.L. CORRIDOR	LVT	VB	P	P	P	P	P	P		ACT II	
669	NURSING CORRIDOR	LVT	VB	P	P	P	P	P	P		ACT II	
670	MECH	SG	VB2	P1	P1	P1	P1	P	P		P	
GROUND FLOOR RESIDENT APARTMENTS												
A.L. ONE BED	LIVING ROOM	LVT1	VB8	P	P	P	P	S1	P14		P	
	BEDROOM	LVT1	VB8	P	P	P	P	S1	P14		P	
	CLOSET	LVT1	VB8	P	P	P	P	S1	P14		P	
	BATHROOM	LVT1	VB8	P	P	P	P	S1	P14		P	
A.L. STUDIO	LIVING / BED ROOM	LVT1	VB8	P	P	P	P	S1	P14		P	
	CLOSET	LVT1	VB8	P	P	P	P	S1	P14		P	
	BATHROOM	LVT1	VB8	P	P	P	P	S1	P14		P	
GROUND FLOOR NURSING HOME ROOMS												
	BEDROOM	LVT1	VB8	P5**	P5**	P5**	P5**	S1	P14		P	
	BATHROOM	LVT	VB1	P6	P6	P6	P6	S1	P14		P	
FIRST FLOOR												
132	OFFICE	G	VB	P1	P1	P1	P1	S1	P14		ACT I	
135	ELEVATOR LOBBY	G	VB	P1	P1	P1	P1	S1	P14	P	ACT II	
146	DINING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING		EXISTING	
148	TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	S1	P14		ACT I	
149	MGR. OFFICE	G	VB	P	P	P	P	S1	P14		ACT I	
150	PHYSICAL THERAPY	G	WB	P	P	P	P	S1	P14	P	ACT II	
151	OCC THERAPY	VCT	VB	P	P	P	P	S1	P14		EXISTING	
152	NEW OFFICE	G	WB	P	P	P	P	S1	P14		ACT I	
153	NEW OFFICE	G	WB	P	P	P	P	S1	P14		ACT I	
154	NEW OFFICE	G	WB	P	P	P	P	S1	P14		ACT I	
165	NEW MEDICINE	SV	VB	P	P	P	P	S1	P14		ACT I	
166	NEW NURSES STATION	G	VB	P1	P1	P1	P1	S1	P14		ACT II	
167	NEW CLEAN UTILITY	VCT4	VB4	P1	P1	P1	P1	S1	P14		ACT I	
168	JANITOR	VCT4	VB4	P1	P1	P1	P1	S1	P14		P	
169	NEW OFFICE MEETING	G	VB	P1	P1	P1	P1	S1	P14		ACT I	
170	NEW SOILED UTILITY	VCT4	VB4	P1	P1	P1	P1	S1	P14		ACT I	
172	MECH	SG	VB	P1	P1	P1	P1	S1	P14		P	
173	STAIR #3	VCT4*	VB2	P1	P1	P1	P1	S1	P14		P	*VCT4 LANDINGS ONLY, PANS AND RAILS P4A
174	ADMIN. OFFICE	G	VB	P	P	P	P	S1	P14		ACT I	
175	MAILROOM	G	VB	P	P	P	P	S1	P14		ACT I	
176	RECEPTION	G	VB	P	P	P	P	S1	P14		ACT I	
177	COMPUTER LAB	G	VB	P	P	P	P	S1	P14		ACT I	
178	VESTIBULE	G	VB	P	P	P	P	S1	P14		ACT II	
179	LOBBY	LVT	VB	P	P	P	P	S1	P14	P	ACT II	
180	WAITING / LIBRARY	G	VB	P	P	P	P	S1	P14	P	ACT II	
181	JANITOR	SG	VB	P	P	P	P	S1	P14		P	
182	PUBLIC TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	S1	P14		ACT I	
183	MECH	SG	VB	P	P	P	P	S1	P14		P	
184	OFFICE	G	VB	P	P	P	P	S1	P14		ACT I	
185	ELEC / TELE	SG	VB	P	P	P	P	S1	P14		P	

FINISH SCHEDULE

ROOM #	ROOM NAME	FLOOR	BASE	WALLS NORTH	WALLS SOUTH	WALLS EAST	WALLS WEST	DOORS	TRIM	BULK.	CEILING	SPECIAL CONDITIONS
FIRST FLOOR - CONT'D												
186	STAIR #4	VCT4*	VB2	P1	P1	P1	P1	P1B	P14		P	*VCT-4 LANDINGS ONLY, PANS AND RAILS P4A
187	LOUNGE	G / LVT	VB	P	P	P	P	S1	P14	P	ACT II	
188	A.L. CORRIDOR	LVT	VB	P	P	P	P	S1	P14	P	ACT II	
189	NURSING CORRIDOR	LVT1 / LVT	VB8	P3	P3	P3	P3	S1	P14		ACT II	
FIRST FLOOR RESIDENT APARTMENTS												
A.L. ONE BED	LIVING ROOM	LVT	VB	P	P	P	P	S1	P14		P	
	BEDROOM	LVT	VB	P	P	P	P	S1	P14		P	
	CLOSET	LVT	VB	P	P	P	P	S1	P14		P	
	BATHROOM	LVT	VB	P	P	P	P	S1	P14		P	
A.L. STUDIO	LIVING / BED ROOM	LVT	VB	P	P	P	P	S1	P14		P	
	CLOSET	LVT	VB	P	P	P	P	S1	P14		P	
	BATHROOM	LVT	VB	P	P	P	P	S1	P14		P	
FIRST FLOOR NURSING HOME ROOMS												
	BEDROOM	LVT1	VB8	P5**	P5**	P5**	P5**	S1	P14		P	**P6 AGENT PAINT - SEE DETAILS PLACEMENT
	BATHROOM	LVT	VB1	P6	P6	P6	P6	S1	P14		P	
SECOND FLOOR												
270	STORAGE	LVT1	VB8	P	P	P	P	P	P		ACT I	
271	ELEVATOR LOBBY	LVT1	VB6	P	P	P	P	P	P	P	ACT II	
272	JANITOR	VCT	VB	P	P	P	P	P	P		P	
273	PUBLIC TOILET	VCT	VB	P/LAM	P/LAM	P/LAM	P/LAM	P	P		ACT I	
274	MECH	SG	VB	P	P	P	P	P	P		P	
275	OFFICE	G	VB	P	P	P	P	P	P		ACT I	
276	ELEC / TELE	SG	VB	P	P	P	P	P	P		P	
277	LOUNGE	G / LVT	VB6	P	P	P	P	P	P		ACT I	*VCT4 LANDINGS ONLY, PANS AND RAILS P4A
278	STAIR #4	VCT4*	VB2	P1	P1	P1	P1	P1B	P1B		P	
279	CLOSET	LVT1	VB8	P	P	P	P	P	P		ACT I	
280	A.L. COORIDOR	LVT	VB	P	P	P	P	S1	P14	P	ACT II	
SECOND FLOOR RESIDENT APARTMENTS												
A.L. ONE BED	LIVING ROOM	LVT1	VB8	P	P	P	P	P	P		P	
	BEDROOM	LVT1	VB8	P	P	P	P	P	P		P	
	CLOSET	LVT1	VB8	P	P	P	P	P	P		P	
	BATHROOM	LVT1	VB8	P	P	P	P	P	P		P	
A.L. STUDIO	LIVING / BED ROOM	LVT1	VB8	P	P	P	P	P	P		P	
	CLOSET	LVT1	VB8	P	P	P	P	P	P		P	
	BATHROOM	LVT1	VB8	P	P	P	P	P	P		P	
THIRD FLOOR												
330	OFFICE	G	VB	P	P	P	P	P	P		ACT I	
333	NEW MECH	SG	VB	P	P	P	P	P	P		P	
334	EX. DUCTS			P	P	P	P	P	P		P	
335	STORAGE	VCT	VB	P	P	P	P	P	P		ACT I	
336	SERVER	VCT	VB	P	P	P	P	P	P		ACT I	
337	EX. STAIR			P	P	P	P	P	P		EXISTING	
338	ELEVATOR LOBBY	LVT	VB	P	P	P	P	P	P	P	ACT II	
339	JANITOR	SG	VB	P	P	P	P	P	P		P	
340	PUBLIC TOILET	VCT	VB	P	P	P	P	P	P		ACT I	
341	MECH	SG	VB	P	P	P	P	P	P		P	
342	OFFICE	G	VB	P	P	P	P	P	P		ACT I	
343	LOUNGE	G / LVT	VB	P	P	P	P	P	P	P	ACT II	
344	ELEC / TELE	SG	VB	P	P	P	P	P	P		P	
345	STAIR #4	VCT4*	VB2	P1	P1	P1	P1	P1B	P1B		P	*VCT4 LANDINGS ONLY, PANS AND RAILS P4A
346	CLOSET	LVT	VB	P	P	P	P	P	P		ACT I	
347	A.L. CORRIDOR	LVT	VB	P	P	P	P	P	P	P	ACT II	
THIRD FLOOR RESIDENT APARTMENTS												
A.L. ONE BED	LIVING ROOM	LVT1	VB8	P	P	P	P	P	P		P	
	BEDROOM	LVT1	VB8	P	P	P	P	P	P		P	
	CLOSET	LVT1	VB8	P	P	P	P	P	P		P	
	BATHROOM	LVT1	VB8	P	P	P	P	P	P		P	
A.L. STUDIO	LIVING / BED ROOM	LVT1	VB8	P	P	P	P	P	P		P	
	CLOSET	LVT1	VB8	P	P	P	P	P	P		P	
	BATHROOM	LVT1	VB8	P	P	P	P	P	P		P	

LEGEND				
FLOORING	BASE	WALLS	CEILING	MISC
C - CARPET	VB - VINYL BASE	P - PAINT	ACT - ACOUSTIC CEILING TILE	P.LAM - LAMINATE
CT - CERAMIC TILE	WB - WOOD BASE	S - STAIN	P - PAINT	SS - STAINLESS STEEL
LVT - LUXURY VINYL TILE		VWG - VINYL WALL COVERING		
QT - QUARRY TILE		FRP - FIBERGLASS REINFORCED PANEL		
SG -SEALED CONCRETE				
VCT - VINYL COMPOSITE TILE				

NOTES:
1. FLOOR PATTERNS BY OWNER'S INTERIOR DESIGNER.
2. NUMBERS FOLLOWING MATERIALS SHOWN IN SCHEDULE REFER TO FINISHES BY OWNERS INTERIOR DESIGNER.

REVISIONS	BY
1 7/26/19 PERMIT	JJS
REVIEW COMMENTS	

Professional Certification
"I certify that these documents were prepared or approved by me, and that I am duly licensed architect under the laws of the State of Maryland, license number 2002 A, expiration date February 25, 2020."

Lorien Nursing - Elkridge Addition
7615 Washington Blvd
Elkridge, Maryland 21075

FINISH SCHEDULE

DATE	April 4, 2019
SCALE	AS NOTED
DRAWN	
JOB	JOB NUMBER
SHEET	A7.4
OF	SHEETS