

1 FLOOR PLAN - MECHANICAL
S 1/4" = 1'-0"

GENERAL NEW WORK NOTES:

1. REFER TO FOOD SERVICE CONSULTANT DRAWINGS FOR MATERIALS, SPECIFICATION, CAPACITY AND INSTALLATION REQUIREMENTS FOR: ICE MAKER UNIT, REFRIGERATED MERCHANDISE, MAKE-UP AIR SYSTEM, KITCHEN EXHAUST SYSTEM, KITCHEN HOOD, HOOD CONNECTIONS, HOOD FIRE SUPPRESSION SYSTEM, CONTROLS, INTERLOCKS AND SHUT-OFF SWITCHES/VALVES.
2. FIELD COORDINATE FINAL EQUIPMENT LOCATIONS WITH OWNER, EQUIPMENT SUPPLIER AND VENDOR.
3. FIELD COORDINATE AIR DEVICES LOCATION WITH CEILING DEVICES, CEILING FEATURES, MILLWORK AND FLOOR EQUIPMENTS.
4. PROVIDE LOCKABLE COVER FOR THERMOSTAT.


NEW WORK PLAN NOTES: #

1. FIELD COORDINATE WITH KITCHEN HOOD MANUFACTURER REPRESENTATIVE FOR CONNECTION TO KITCHEN HOOD.
2. 3" CONCENTRIC VENT UP THROUGH ROOF. PROVIDE EXHAUST ADAPTOR RING AND INTAKE CAP AS REQUIRED.
3. PROVIDE REFRIGERANT PIPING TO OUTDOOR CONDENSING UNIT ON ROOF.
4. CONNECT 1" CONDENSATE DRAIN LINE TO EVAPORATOR WITH P-TRAP.
5. PROVIDE HEAT TRACE FOR CONDENSATE DRAIN PIPING IN WALK-IN FREEZER. REFER TO ELECTRICAL DRAWINGS FOR HEAT TRACE DETAILS.
6. DISCHARGE CONDENSATE DRAIN PIPING INTO OPEN SITE DRAIN. REFER TO PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.
7. 12"x12" TRANSFER AIR DUCT WITH 1" SOUND LINING.



BR
ENGINEERING SERVICES
502 MC Dr
S 38
G Br, Md 21061
P 410 781-9900
F 410 781-9900
www.br

Pr. Dr.
11/1/17
rsr/rd - d 1
d/g/g/d
w. S. Mds
L.V.
E/D
9920
17 JAN 2019



DASH IN
STORE #079
QUARTERFIELD RD - SEVERN, MD

REV. #	ISSUE / DESCRIPTION	DATE

SHEET TITLE
**FLOOR PLAN
MECHANICAL**

DRAWING DATE:
01 APRIL 2017
DRAWN BY:
MVM
REVIEWED BY:
MGH

PROJECT #
2889
SHEET #



FILE NAME:
2889 - M-101.dwg