UTILITY SCHEDULE

	ITEM	QTY.	DESCRIPTION	MANUFACTURER	MODEL	PROVIDE	INSTALL	ELECTRICAL CONN.	NEMA	VOLTS	PH	AMP	HP	KW	HGT.	DRAIN	PLUMBING I.W.	D.W.	HGT.	C.W.	H.W.	HGT.	CH.W. SUP.	HGT.	CH.W RET.	HGT.	GAS	MBTU	HGT.	PSIG.	STEAM SUP.	HGT.	STEAM RET.	REMARKS
DISPENSED BEVERAGE	101	1	FREAL REFRIGERATED CASE	FREAL	22-1156-X1-FRL-2	O	V	CORD & PLUG	5-15P	120		10.5			24"																				REQUIRES A 15AMP DEDICATED CIRCUIT. GOODE REFRIGERATION, LEFT HINGE. (EXISTING)
	102	1	FREAL BLENDER ON SIDE COUNTER	FREAL	FRLB4	O	V	CORD & PLUG	5-15P	120		10.5			24"																				REQUIRES A 15AMP DEDICATED CIRCUIT. GOODE REFRIGERATION, LEFT HINGE
	103	1	FROZEN BEVERAGE DISPENSER (ICEE)	FBD	563	O	V	CORD & PLUG	L6-20P	208	1	20.0			54"	FS	1/2"			3/8"		48"												GOODE REFRIGERATION, LEFT HINGE
	104A	-	SODA DISPENSER	LANCER	IBD 4500-60	E	V																											GOODE REFRIGERATION, INSTALL 16 VALVE W/ ICE DISPENSERS
	104B	1	TOUCHPOINT BEVERAGE DISPENSER	LANCER	TOUCHPOINT	E	V	CORD & PLUG	5-15P	120		6.0			54"	FS	1/2"																	GOODE REFRIGERATION
	105	1	ICE MAKER	CORNELIUS	KCC-1401R	E	V	DIRECT	JB	120		20.0			64"	FS	3/8"			1/4"		64"												GW SUPPLY FROM WATER FILTER CONNECTION "B" ITEM 616 - GOODE REFRIGERATION INSTALLS
	105A	1	ICE MAKER - REMOTE CONDENSER	CORNELIUS	KCU-1401	E	V	DIRECT	JB	208		20.0			ROOF																			* CONDENSER LOCATED ON ROOF. GOODE REFRIGERATION
	106	6	BUILT-IN CUP DISPENSER	MILLWORK-VENDOR	--	M	G																											INTEGRATED IN CUSTOM MILLWORK
	107	-	LID HOLDER	DISPENSE-RITE	TLO-4BT	E	M																											
	108	1	DOME LID HOLDER WITH STRAWS	DISPENSE-RITE	FMVDL-3	E	G																											INSTALLED BY GC.
	109	9	TRASH CAN	MILLWORK-VENDOR	--	M	M																											INTEGRATED IN CUSTOM MILLWORK
	110	1	BUILT-IN LID ORGANIZER	DISPENSE-RITE	FMVL-4	E	G																											INSTALLED BY GC.
	111	4	BUILT-IN STRAW HOLDER	DISPENSE-RITE	FMVS-1	E	G																											
	112	-	NOT USED	--	--																													
COFFEE	201	2	COFFEE BREWER	CURTIS	GEMTFIO1A1000	O	V	DIRECT	JB	208	1	23.6		5.2	54"					3/8"		54"												GW SUPPLY FROM WATER FILTER CONNECTION "B" ITEM 616 - GOODE REFRIGERATION INSTALLS
	202	4	COFFEE WARMER - STAND	CURTIS	GEM3IF	O	V	CORD & PLUG	5-15P	120		5.4		.071	24"																			
	202A	10	COFFEE SATELLITES	CURTIS	GEM3IF	O	V	CORD & PLUG	5-15P	120		.6		.071	24"																			
	203	1	LATTE (CAPUCCINO)	BUNN	IMIX-5-HH-BLK	E	G	CORD & PLUG	5-15P	120		15		1.8	42"					3/8"		42"												INCLUDES HOT WATER DISPENSER
	204	1	HAND SINK	ADVANCE TABCO	DI-1-105P	E	G									FS	1-1/2"			1/2"	1/2"	18"												DROP-IN W/ REAR & SIDE SPLASH GUARD (10"DEEP) W/ K-52 FAUCET, INSTALL BY GC.
	205	4	COFFEE CONDIMENTS	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	206	2	CREAMER	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	207	-	NOT USED	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	208	2	FLAVOR SHOTS	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	209	2	HOT TEA BAG HOLDER	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	210	-	NOT USED	--	--																													
	211	2	COFFEE ACCESSORIES	NOVAK BIRCH	--	V	O																											CUSTOM SMALL WARES
	212	1	THE CREAM MACHINE	GOODNEST	GMB TRIPLE	O	V	CORD & PLUG	5-15P	120		2.0		0.15	48"																			GOODE REFRIGERATION, INSTALLS
	213	-	NOT USED	--	--																													
	214	-	NOT USED	--	--																													
GRILL BAR	301	1	ROLLER GRILL	STAR	T55C	E	V	CORD & PLUG	5-20P	120		14.4		1.73	42"																			GOODE REFRIGERATION, INSTALLS
	302	1	DROP-IN COLD PAN	HATCO	GNB-1	E	V	CORD & PLUG	5-15P	120		6.7	1/4	0.8	24"	FS	1"																	19"X27"X25.5"
	303	1	NACHO RACK	--	--	E	O																											SMALL WARES
	304	1	CHEESE DISPENSER	STAR	HPDE2	O	V	CORD & PLUG	5-15P	120		8.5		1.0	42"																			GOODE REFRIGERATION
	305	1	CONDIMENTS & UTENSILS	--	--	V	O																											SMALL WARES
	306	-	NOT USED	--	--	O	O																											INSTALL CUSTOM SMALL WARES
	307	1	UNDER CABINET REFRIGERATOR	TRUE	TUC-36-LP	O	V	CORD & PLUG	5-15P	120		6.1	1/6		24"																			GOODE REFRIGERATION, LOW PROFILE FROM ATTIC STOCK
	308	-	NOT USED	--	--																													
	309	1	SNEEZE GUARD	MILLWORK-VENDOR	--	M	M																											
CENTER STORE	401	1	WALK-IN COOLER	GROWNTONKA	--	O	--	DIRECT	(2) JB	120		15.0			110"																			LIGHTS, ALARMS, & DOOR HEATERS GOODE TO INSTALL
	401A	1	CONDENSING UNIT- COOLER	HUSSMANN	TBD	E	V	DIRECT	JB	208	3		3	7.3	ROOF																			
	401B	2	EVAPORATOR COIL- COOLER	HUSSMANN	TBD			DIRECT	JB	208	1	2.7			108"	FFD	3/4"																		
	401C	8	48"X24" WIRE SHELVING	NEXTEL	--																													
	401D	1	60"X24" WIRE SHELVING	NEXTEL	--																													
	402	1	WALK-IN FREEZER	GROWNTONKA	--	E	V	DIRECT	(2) JB	120		15.0			110"																			LIGHTS, ALARMS, DOOR HEATERS & HEAT TAPE. GOODE TO INSTALL
	402A	1	CONDENSING UNIT- FREEZER	HUSSMANN	TBD			DIRECT	JB	208	3	35.75	5.02	9.9	ROOF																			CONTROL WIRING & POWER SUPPLY INTERCONNECTED WITH ITEM 402B
	402B	1	EVAPORATOR COIL - FREEZER	HUSSMANN	CUSTOM			DIRECT	JB	208	1	26.1		5.43	108"	FFD	3/4"																	CONTROL WIRING & POWER SUPPLY INTERCONNECTED WITH ITEM 402A
	403A	1	BAKERY CASE	CAYUGA	CUSTOM	V	V	DIRECT	JB	120		5.0			12"																			GOODE TO INSTALL. LED LIGHTS
	403B	1	BAKERY CASE	CAYUGA	CUSTOM	V	V																											GOODE TO INSTALL
	404A	1	REFRIGERATED MERCHANDISER	SOUTHERN	7-MDI-04VNT-R	V	V	DIRECT	JB	120		1.36			*	FS	1/2"																	*(STUB-UP) LIGHTS
		1	REFRIGERATED MERCHANDISER	SOUTHERN	7-MDI-04VNT-R	V	V	DIRECT	JB	120		1.04			*																			FANS
	404B	-	NOT USED	--	--																													
	404C	1	REFRIG. MERCHANDISER - REMOTE- CONDENSER - ON ROOF	KEEPRITE	KEHA025E6-HS2B	V	V	DIRECT	JB	208	1	12.3	2.5		*																			LOCATED ON ROOF. REMOTE CONDENSING UNIT. GOODE TO INSTALL
	405	1	HOT FOOD MERCHANDISER	HENNY PENNY	EPC300	E	V	CORD & PLUG	6-20P	208	1	17.2		3.57	24"																			GOODE TO INSTALL, FLOOR MOUNTED
	406	-	36" GONDOLA SHELVING W/ 18" END CAPS	CAYUGA	--	V	V																											GOODE TO INSTALL 54" TALL FIXTURE
	407	3	72" GONDOLA SHELVING W/ 18" END CAPS	CAYUGA	--	V	V	DIRECT	JB	120		5.0			0"																			GOODE TO INSTALL 72" TALL FIXTURE W/ 18" DRAWERS - LIGHTS- (ELECTRICAL STUB-UP REQUIRED)
	408	-	108" GONDOLA SHELVING W/ 18" END CAPS	CAYUGA	--	V	V																											GOODE TO INSTALL 54" TALL FIXTURE
	409	-	IN-QUEU MERCHANDISER	CAYUGA	--	V	V																											GOODE TO INSTALL 54" TALL FIXTURE
	410	-	36" SINGLE SIDED SHELVING	CAYUGA	--	V	V																											GOODE TO INSTALL 60" TALL FIXTURE @ OTB
	411	-	48" SINGLE SIDED SHELVING	CAYUGA	--	V	V																											GOODE TO INSTALL 54" TALL FIXTURE
	412	1	36" SINGLE SIDED SHELVING	CAYUGA	--	V	V																											GOODE TO INSTALL 54" TALL FIXTURE
	413	1	60" SINGLE SIDED SHELVING	CAYUGA	--	V	V	DIRECT	JB	120		5.0			0"																			GOODE TO INSTALL 54" TALL FIXTURE - LIGHTS- (ELECTRICAL STUB-UP REQUIRED)
	414	1	72" GONDOLA SHELVING	CAYUGA	--	V	V	DIRECT	JB	120		5.0			0"																			GOODE TO INSTALL 54" TALL FIXTURE - LIGHTS- (ELECTRICAL STUB-UP REQUIRED)
FOOD LINE / FOOD PREP.	501	1	SANDWICH PREP TABLE	RANDELL	826BN	E	V	CORD & PLUG	5-15P	120		9.0	1/3		24"																			GOODE REFRIGERATION, WITH GLASS TOP & DRAWERS
	502	1	HAND SINK	ADVANCE TABCO	SHK-302	E	G									FS	1-1/2"			1/2"	1/2"	18"												
	503	-	NOT USED	--	--																													
	504	1	EXHAUST HOOD	CAPTIVE-AIRE	DWG# 2722058	V	V	DIRECT	JB	120		15.0			84"																			
	505	1	SPEED RACK	CHANNEL	R1X-I3	E	V																											
	506	1	GAS GRIDDLE 6'-0"	VULCAN	MSAT2	E	V																					3/4"	162.0	6"				
	507	1	REFRIGERATOR GRIDDLE STAND	CONTINENTAL REFRIG	DL72G	E	V	CORD & PLUG	5-15P	120		6.1	1/4		24"																			
	508	1	GAS FRYER - (BATTERY)	PITCO	SG14S-2FD	E	V	CORD & PLUG	5-15P	120		1.7/1.0			24"													1"	220.0	6"				FILTER/ CONTROLS
	509	1	MICROWAVE	ACP	HDC12A2	E	V	CORD & PLUG	5-20P	120		16.8		2.0	54"																			
	510	-	ENCLOSED BASE, WORK TABLE WITH DRAWERS	ADVANCE TABCO	EK-55-308	E	V																											
	510B	1	ENCLOSED BASE, WORK TABLE WITH DRAWERS	ADVANCE TABCO	EK-55-306	E	V																											
	511	1	REFRIGERATOR, UNDERCOUNTER	TRUE	TUC-48-LP-HC	E	V	CORD & PLUG	5-15P	120		3.0	1/5		24"																			
	512	1	WORKTOP FREEZER	TRUE	TWT-48F-HC	E	V	CORD & PLUG	5-15P	120		5.4	1/2		24"																			
	513	1	CONVECTION OVEN	MERRYCHEF	E45	E	V	CORD & PLUG	6-30P	208	1	30.0		6.2	54"																			
	514	3	MADE TO ORDER PRINTER	RADIANT	--	O	V	CORD & PLUG	5-15P	120		15.0			48"																			REQUIRES A DEDICATED & ISOLATED QUAD RECEPTACLE & DATA CONNECTION
	515	3	ORDER SYSTEM MONITOR	RADIANT	UNKNOWN	O	O	CORD & PLUG	5-15P	120		15.0			CLG.																			REQUIRES A DEDICATED & ISOLATED QUAD RECEPTACLE & DATA CONNECTION. INTERCONNECT TO MAC VICTOR
	516	2	ORDER SYSTEM KIOSK W/ PRINTER	RADIANT	--	O	O	CORD & PLUG	5-15P	120		15.0			48"																			REQUIRES A DEDICATED & ISOLATED QUAD RECEPTACLE & DATA CONNECTION
	517	1	HALF-SIZE ELECTRIC CONVECTION OVEN	VULCAN	EC02D	E	O	DIRECT	JB	208	1	26	1/3	5.5	54"																			

L2M
811 Cromwell Park Drive, Suite 113
Cromwell Business Park at BWI
Glen Burnie, Maryland 21061

www.L2Mfoodservicedesign.com

Phone 410.863.1302
Fax 410.863.1308

L2M
FOODSERVICE
DESIGN GROUP

DASH IN
STORE # 079
QUARTERFIELD RD - SEVERN, MD

REV. #	ISSUE / DESCRIPTION	DATE

SHEET TITLE:
FOODSERVICE EQUIPMENT UTILITY LOAD SCHEDULE

DRAWING DATE:
01 APRIL 2017

DRAWN BY: L2M | REVIEWED BY: SOC

JOB NUMBER:
15.108

SHEET #:
FS 2

FILE NAME:
15.108 PLAN SCHEDULE dwg