



18076069  
REVIEWED FOR COMPLIANCE

Performance of this review does not relieve the applicant from full responsibility to comply with all applicable codes, ordinances and regulations 10/29/18

**JOHNSON-LANCASTER AND ASSOCIATES, INC.**  
FOOD SERVICE EQUIPMENT SPECIALIST  
13031 US Highway 19 N Clearwater, FL 33764 (727) 796-5622

REVISIONS NUMBER	DATE	DESCRIPTION
1	10/19/18	PER HEALTH DEPARTMENT COMMENTS
2	10/24/18	PER HEALTH DEPARTMENT COMMENTS

UTILITY SCHEDULE

ITEM NO	QTY	EQUIPMENT CATEGORY	MANUFACTURER	MODEL NUMBER	PLUG DIRECT	VOLTS	PHASE	AMPS	KW	HP	NEMA	HOT WATER SIZE (IN)	HOT WATER GPH	COLD WATER SIZE (IN)	DIRECT DRAIN SIZE (IN)	INDIR DRAIN SIZE (IN)	GAS SIZE (IN)	MBTUH	EQUIPMENT REMARKS
LB-01	1	UNDERBAR COCKTAIL STATION	PERLICK	PTE80-A								1/2		(3)1/2	(4)1-1/2				
LB-02	1	UNDERBAR SPEED RAIL	PERLICK	SR-H36A															
LB-03	1	GLASSWASHER	PERLICK	PKBR24	X	120	1	5.4	0.6		5-15P	1/2				1 1/4			
LB-04	1	UNDERBAR HANDSINK	PERLICK	TS18HSN								3/8		3/8		1 1/2			
LB-05	1	DISPENSER, BEER	PERLICK	DDC92	X	120	1	6.3		1/3	5-15P					(2)1			
LB-06	2	UNDERBAR DRY STORAGE	PERLICK	7055A-D															
LB-07	3	SLIM JIM TRASH CAN		FG3500BLK															
LB-08	1	SPARE NUMBER																	
LB-09	1	UNDERBAR COCKTAIL ICE CHEST	PERLICK	TSC36IC10															
LB-10	1	UNDERBAR COCKTAIL STATION	PERLICK	PTE68-A								1/2		(3)1/2	(4)1-1/2				
LB-11	2	BACK BAR EQUIPMENT	PERLICK	BBS60**LD	X	120	1	5.5		1/4	5-15P								
LB-12	2	POS SYSTEM	BY OTHERS	BY OTHERS	X	120	1	5.0			5-15P								
LB-13	1	SPARE NUMBER																	
LB-14	1	SPARE NUMBER																	
LB-15	1	MILLWORK BEVERAGE STATION CABINET	MILLWORK	CUSTOM															
LB-15.1	1	DRIP TROUGH	FABRICATOR	CUSTOM															
LB-16	1	SODA, ICE & BEVERAGE DISPENSER	BY VENDOR	BY VENDOR	X	115	1	10.0			5-15P			3/4		3/4			
LB-17	1	COFFEE MAKER, AIRPOT, AUTOMATIC	BUNN-O-MATIC	BY VENDOR	X	120	1	15.4						1/2		1/2			
LB-17.1	3	DISPENSER, ICE TEA/ICE COFFEE	BUNN-O-MATIC	BY VENDOR															
LB-18	1	HAND SINK	EAGLE	HWC-E								1/2		1/2	1-1/2				
RB-01	1	SPARE NUMBER																	
RB-02	3	UNDERBAR DRY STORAGE	PERLICK	7055A-D															
RB-03	1	UNDERBAR LIQUOR DISPLAY	PERLICK	7055A3															
RB-04	1	UNDERBAR HANDSINK	PERLICK	TS12HSN								3/8		3/8		1 1/2			
RB-05	1	UNDERBAR COCKTAIL ICE CHEST	PERLICK	TSC36IC10												1/2			
RB-06	1	UNDERBAR SPEED RAIL	PERLICK	SR-H36A															
RB-07	1	BACK BAR EQUIPMENT	PERLICK	BBS92**R	X	120	1	6.3		1/3	5-15P								
RB-08	2	POS SYSTEM	BY OTHERS	BY OTHERS	X	120	1	5.0			5-15P								
RB-09	1	SPARE NUMBER																	
RB-10	1	SPARE NUMBER																	
RB-11	1	SPARE NUMBER																	
RB-12	1	SPARE NUMBER																	
RB-13	1	ICE MAKER	MANITOWOC ICE	MD1-1500A-261	X	208-230	1	15.4						1/2					
RB-13.1	1	ICE BIN	MANITOWOC ICE	F-1300												1			
RB-13.2	1	WATER FILTER SYSTEM	MANITOWOC ICE	AR-40000										3/8					
RB-13.3	1	FLOOR TROUGH	BY G.C.	BY G.C.												3			
RB-14	1	SPARE NUMBER																	

void

- NOTE:**
- ALL CONNECTIONS SHOWN IN THE SCHEDULE ARE SIZED AS THEY ACTUALLY OCCUR ON THE EQUIPMENT.
  - CONNECTIONS SHOWN ARE FOR ONE UNIT. TO DETERMINE TOTAL REQUIREMENTS, MULTIPLY BY NUMBER IN QUANTITY COLUMN.
  - ELECTRIC CONTRACTOR AND PLUMBING CONTRACTOR TO VERIFY UTILITIES ON EXISTING EQUIPMENT AND EQUIPMENT NOT IN FOODSERVICE CONTRACT.
  - WHERE INDICATED TO CONNECT IN OR THROUGH A VALVE COMPARTMENT, CONTRACTOR SHALL STUB-UP INTO VALVE COMPARTMENT AT HEIGHT INDICATED ON ROUGH-IN PLAN, CAP HIS WORK AND MAKE FINAL CONNECTIONS AFTER EQUIPMENT IS IN PLACE.
  - THE INTENT OF THE DRAWINGS AND SPECIFICATIONS REGARDING ELECTRICAL PRE-WIRING AND PLUMBING PRE-PIPING IS TO HAVE THE K.E.C. EXTEND TO AND TERMINATE ALL CONNECTIONS FOR THE EQUIPMENT IN THE LOCATIONS INDICATED IN THE EQUIPMENT SCHEDULE AND SPOT PLANS.
  - ELECTRICAL, PLUMBING AND MECHANICAL CONTRACTORS TO PROVIDE ALL ROUGH-IN BUILDING SERVICES AND FINAL CONNECTION TO ALL FOOD SERVICE EQUIPMENT.

OUZO RESTAURANT & LOCH BAR  
HOUSTON, TEXAS

PROJECT TITLE:

DATE:	06/28/2017
SCALE:	1/4" = 1'-0"
DRAWN BY:	JR
DESIGNED BY:	JR
PAPER SIZE:	24x36
EQUIPMENT SCHEDULE	
SHEET:	FS-1.1