

NEW VARIABLE VOLUME TERMINAL BOX SCHEDULE

DESIGNATION	1	15	21	24	25	26	27	28	31	35	36	37	38	39	41	43	44	45	49	50	51	56	57	60	80	81	82	83	
SPACE NUMBER	1116	2141	2116A	2125	2124	2123	2122	2111	2117	2212	2207	2210	2201	2210	2212	2148	2148	2165	2177	2179	2194	2184	2181	2187	2132	2132E	2132E	2136	
CFM	750	815	350	1156	533	731	485	538	491	837	1586	770	872	770	837	600	600	2936	760	806	794	835	1079	501	666	625	625	1170	
MIN SUPPLY CFM	486	326	113	463	267	366	194	265	246	420	397	273	436	273	420	328	328	1100	380	403	199	335	270	125	333	250	250	470	
MAX SP-H ₂ O	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	
SOUND POWER LEVEL (NC) - MAX.	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	
MODEL VCVF	08	08	05	10	08	08	08	06	08	08	12	08	08	08	08	08	14	08	08	08	08	08	08	08	08	08	08	10	
DUCT RUN-OUT SIZE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	14"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	
REHEAT COIL																													
BTU HR	18,983	13,706	5886	19,441	8480	14,295	9472	8913	8274	14,127	26,673	12,950	14,665	12,950	14,665	11,365	11,365	49,376	12,781	13,555	13,353	14,043	18,146	8488	13,730	8951	8951	16,981	
ENT WTR TEMP (F)	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"
GPM	1.9	1.4	0.6	1.9	0.9	1.4	0.9	0.9	0.9	0.8	1.4	2.7	1.3	1.5	1.3	1.5	1.1	1.1	4.9	1.3	1.3	1.4	1.8	0.8	1.4	0.9	0.9	1.7	
ROWS	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D
WTR PD FT. (MAX.)	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
EAT DB.	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F
LAT DB.	85°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F
PIPING RUN-OUT SIZE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING

REMARKS: (ALL NOTES APPLY TO ALL BOXES)

① ALL BOXES TO BE PRESSURE INDEPENDENT. ③ ALL BOXES TO BE EQUIPPED WITH DDC AUXILIARY TEMPERATURE SENSOR. ⑤ CONTRACTOR TO VERIFY ALL VALVE BOX NUMBERS MATCH SPACE NUMBERS AS INDICATED ON SCHEDULE.
 ② DUCT RUN-OUT SIZE DOES NOT MEAN INLET BOX SIZE. ④ SEE SHEET M-504 FOR VAV BOX PLENUM DETAIL (CONNECTIONS TO DIFFUSERS).
 A TRANSITION MAY BE REQUIRED.

NEW VARIABLE VOLUME TERMINAL BOX SCHEDULE

DESIGNATION	84	85	89	90	92	99	101	103	104	114	115	117	125	134	136	138	139	142	145	153	156	159	160	161	162	163	165	166	
SPACE NUMBER	2133	2128	2132	2132	2129	2107	2120	2109	2109A	2199	2208	2208	2150A	2150D	2149	2151	2151	2151B	2176	2160B	2162	2218	2218	2217	2211	2115	2205	2205	
CFM	1321	1121	666	666	904	1130	1567	507	435	1420	813	637	93	1151	573	573	178	726	646	109	475	475	750	887	797	548	548		
MIN SUPPLY CFM	667	490	333	333	226	619	627	80	200	675	407	407	255	24	378	144	144	89	271	258	40	194	194	214	222	399	274	219	
MAX SP-H ₂ O	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	
SOUND POWER LEVEL (NC)	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	
MODEL VCVF	10	10	08	08	08	10	12	06	06	14	08	08	08	04	08	08	08	04	08	08	08	08	08	08	08	08	08	08	08
DUCT RUN-OUT SIZE	12"	12"	EXISTING	EXISTING	EXISTING	12"	EXISTING	8"	8"	14"	EXISTING	EXISTING	EXISTING	EXISTING	12"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	
REHEAT COIL																													
BTU HR	22,216	18,852	13,730	13,730	15,203	20,820	28,053	8527	7315	27,733	13,689	13,689	12,440	1564	19,660	9636	9636	2993	11,751	12,616	1833	9277	7988	14,648	17,323	13,403	9216	7366	
ENT WTR TEMP (F)	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"
GPM	2.2	1.9	1.4	1.4	1.5	2.1	2.8	0.9	0.7	2.8	1.4	1.4	1.2	0.2	1.9	1.0	1.0	0.3	1.2	1.3	0.2	0.9	0.8	1.5	1.7	1.3	0.9	0.7	
ROWS	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D
WTR PD FT. (MAX.)	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
EAT DB.	49°F	49°F	47°F	47°F	49°F	49°F	47°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F
LAT DB.	80°F	80°F	85°F	85°F	80°F	80°F	80°F	80°F	80°F	85°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	85°F	80°F	80°F	80°F	85°F	80°F	85°F	80°F	80°F
PIPING RUN-OUT SIZE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING

REMARKS: (ALL NOTES APPLY TO ALL BOXES)

① ALL BOXES TO BE PRESSURE INDEPENDENT. ③ ALL BOXES TO BE EQUIPPED WITH DDC AUXILIARY TEMPERATURE SENSOR. ⑤ CONTRACTOR TO VERIFY ALL VALVE BOX NUMBERS MATCH SPACE NUMBERS AS INDICATED ON SCHEDULE.
 ② DUCT RUN-OUT SIZE DOES NOT MEAN INLET BOX SIZE. ④ SEE SHEET M-504 FOR VAV BOX PLENUM DETAIL (CONNECTIONS TO DIFFUSERS).
 A TRANSITION MAY BE REQUIRED.

NEW VARIABLE VOLUME TERMINAL BOX SCHEDULE

DESIGNATION	167	168	169	170	171A	174	176	180A	181A	184	185	188	189	191	192	193	196	197	198	199	200	202	203	205	207	208	215	220	
SPACE NUMBER	2203B	2203A	2119	2119	1178	1186	1186	1126	1126	1125A	1125B	1135	1137	1172	1190	1190	1196	1196	1212C	1212	1212B	1205	1204	205	207	208	215	220	
CFM	744	731	320	320	1609	1120	1120	1911	1911	346	346	498	959	1708	592	592	492	492	2408	493	394	918	1339	960	1418	1120	1044		
MIN SUPPLY CFM	372	366	155	155	646	450	450	955	955	173	173	182	240	854	174	174	194	194	641	123	99	230	230	240	709	353	313		
MAX SP-H ₂ O	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	
SOUND POWER LEVEL (NC)	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	35	
MODEL VCVF	08	08	05	05	12	10	10	12	12	05	05	06	10	12	08	08	06	06	16	06	06	10	10	10	10	10	10	10	
DUCT RUN-OUT SIZE	EXISTING	EXISTING	EXISTING	EXISTING	14"	EXISTING	EXISTING	14"	14"	EXISTING	EXISTING	EXISTING	12"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	18"	9"	9"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	
REHEAT COIL																													
BTU HR	14,530	14,276	5382	5382	27,059	15,136	15,136	37,322	37,322	5819	5819	8375	16,128	28,724	9956	9956	8274	8274	40,497	8291	6626	15,439	15,439	22,535	18,949	23,847	18,836	17,558	
ENT WTR TEMP (F)	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"	180"
GPM	1.5	1.4	0.5	0.5	2.7	1.5	1.5	3.7	3.7	0.6	0.6	0.8	1.6	2.9	1.0	1.0	0.8	0.8	4.0	0.8	0.7	1.5	1.5	2.3	1.9	2.4	1.9	1.8	
ROWS	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D	AS REQ'D
WTR PD FT. (MAX.)	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
EAT DB.	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	47°F	47°F	47°F	47°F	47°F	47°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F	49°F
LAT DB.	85°F	85°F	80°F	80°F	80°F	80°F	80°F	85°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	80°F	85°F	80°F	80°F	80°F
PIPING RUN-OUT SIZE	EXISTING	EXISTING	EXISTING	EXISTING	3/4"	EXISTING	EXISTING	1"	1"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	1"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING

REMARKS: (ALL NOTES APPLY TO ALL BOXES)

① ALL BOXES TO BE PRESSURE INDEPENDENT. ③ ALL BOXES TO BE EQUIPPED WITH DDC AUXILIARY TEMPERATURE SENSOR. ⑤ CONTRACTOR TO VERIFY ALL VALVE BOX NUMBERS MATCH SPACE NUMBERS AS INDICATED ON SCHEDULE.
 ② DUCT RUN-OUT SIZE DOES NOT MEAN INLET BOX SIZE. ④ SEE SHEET M-504 FOR VAV BOX PLENUM DETAIL (CONNECTIONS TO DIFFUSERS).
 A TRANSITION MAY BE REQUIRED.

AHU UNIT SCHEDULE

UNIT NUMBER	NEW 1	NEW 2	NEW 3	NEW 4	NEW 5	NEW 6	EXISTING 7 (4)	EXISTING 8 (4)	NEW 9	NEW 10	NEW 11	NEW 12	NEW 13	NEW 14	NEW 15	NEW 16	NEW 17	NEW 18	EXISTING 19 (4)	EXISTING 20 (4)	NEW 21	EXISTING 22	NEW 23	NEW 24	EXISTING 26 (4)	NEW 27	NEW 28	NEW 29	
MANUFACTURER	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	TRANE	
MODEL																													
TOTAL AIR FLOW (cfm)	1065	1072	1079	1086	2722	23,019	13,793	2861	6819	12,095	3128	5516	4869	7313	9771	5042	9956	7106	10,553	24,037	21,155	3375	1356	24,160	21,543	10,195	11,028	925	
TOTAL COOLING CAPACITY (MBH)	47.39	47.7	47.65	47.96	137.9	1069.97	---	188.0	381.11	668.84	129.79	390.36	234.76	399.13	444.4	227.74	480.23	285.38	634.9	1583.5	905.38	81.3	63.56	978.17	1199.2	429.54	453.81	60.79	
OUTSIDE AIR (min. cfm)	240	240	240	240	1000	5616	2155	373	1514	4834	555	3777	1603	2831	2769	1185	2820	1335	4131	10,797	4946	225	360	4638	6888	2272	2106	524	
MINIMUM AIR FLOW (cfm)	1065	1072	1079	1086	1239	9475	4820	1144	6819	6410	1251	4253	1981	2925	3699	2017	3982	2198	4538	13,220	7638	3375	1356	9086	8617	3520	5319	925	
TYPE	CV	CV	CV	CV	VAV	VAV	VAV	VAV	CV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	VAV	CV	CV	VAV	VAV	VAV	VAV	VAV	CV
FILTER:																													
TYPE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	30% ROUGHING 85% CARTRIDGE	
SUPPLY FAN:																													
TYPE	FC	FC	FC	FC	BI	AF	AF	AF	BI	BI	BI	BI	BI	BI	BI	BI	BI	BI	AF	AF	AF	FC	FC	AF	AF	AF	BI	AF	FC
TOTAL S.P. (in. H ₂ O)	3.31	3.33	3.32	3.32	4.42	4.93	5.79	3.51	4.07	5.11	3.27	3.51	3.61	3.94	3.7	3.73	3.88	3.99	5.31	5.59	4.17	4.38	3.98	4.81	6.28	3.38	3.86	3.03	
MAX. FAN RPM	2040	2047	2047	2047	2081	1338	1778	1882	1754	2233	1485	2468	1640	1447	2308	1501	2443	1186	2197	2297	1186	1223	1307	1307	1382	1426	1956	15	
MIN. MOTOR HP	2	2	2	2	5 (1)	30 (1)	6 (1)	3 (6)	10	20 (1)	5 (1)	7.5 (1)	7.5 (1)	18 (1)	10 (1)	15 (1)	18 (1)	25 (6)	40 (6)	25 (1)	18 (6)	2	30 (1)	48 (6)	5 (1)	1.5	1.5		
ELECTRICAL	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3
EXTERNAL S.P. (in. H ₂ O)	0.6	0.6	0.6	0.6	1.4	1.4	1.4	1.2	0.7	1.7	1.0	1.0	1.0	1.0	0.9	0.9	1.0	0.9	1.40	1.83	1.5	0.25	0.65	1.5	1.73	1.0	1.3	0.6	
MODIFICATIONS	NEW	NEW	NEW	NEW	NEW	NEW	EXISTING (2)	EXISTING (2)	NEW	NEW	NEW	NEW	NEW	NEW	NEW	NEW	NEW	NEW	EXISTING (2)	EXISTING (2)	NEW	EXISTING (2)	NEW	NEW	EXISTING (2)	NEW	NEW	NEW	NEW
RETURN FAN:																													
TYPE	*	*	*	*	FC	FC			*	FC	BI	BI	BI	BI	BI	BI	BI	BI	AF	AF	AF	FC	FC	AF	AF	BI	BI	AF	
CFM	*	*	*	*	1722	21821	11638	2491	*	6999	2970	1741	3266	5399	7061	4849	9578	5771	8452	2122	16209	*	*	19622	2047	7923	8922	*	
TOTAL S.P. (in. H ₂ O)	*	*	*	*	2.55	2.72	1.65	1.38	*	2.58	1.58	1.38	1.79	1.71	1.68	1.91	1.86	2.17	1.85	2.41	2.33	*	*	2.6	2.13	1.86	1.98	*	
MAX. FAN RPM	*	*	*	*	1583	1092			*	1446	1759	1240	1556	1119	1009	1921	1187	1779			917	*	*	1825	1090	1166	*		
MIN. MOTOR HP	*	*	*	*	2 (1)	15 (1)	10 (6)	1 (6)	*	5 (1)	2 (1)	1 (1)	2 (1)	3 (1)	5 (1)	3 (1)	5 (1)	5 (1)	7.5 (6)	15 (6)	10 (6)	*	*	15 (1)	20 (6)	5 (1)	5	*	
ELECTRICAL	*	*	*	*	460/3	460/3	460/3	460/3	*	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3	460/3
MODIFICATIONS	*	*	*	*	NEW	NEW	EXISTING (2)	EXISTING (2)	*	NEW	NEW	NEW	NEW	NEW	NEW	NEW	NEW	NEW	EXISTING (2)	EXISTING (2)	NEW	EXISTING (2)	NEW	NEW	EXISTING (2)	NEW	NEW	NEW	NEW
HEATING COIL:																													
SERVICE	RE-HEAT (1)	RE-HEAT (1)	RE-HEAT (1)	RE-HEAT (1)	HEAT	HEAT			RE-HEAT (1)	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	HEAT	RE-HEAT (1)	RE-HEAT (1)	HEAT	HEAT	HEAT	HEAT	RE-HEAT (1)	
TYPE	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER			HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	HOT WATER	
MAX. FACE VELOCITY (fpm)	500	500	500	500	500	500			500	600	600	600	600	600	600	600	600	600	600	600	600	600	600	600	600	600	600	600	
EAT/LAT (F.)	55.2/90	55.3/90	55.3/90	55.4/90	11/55	11/55			55.3/90	11/55	11/55	11/55	11/55	11/55	11/55	11/55	11/55	11/55	11/55	11/55	11/55	53.1/90	52.9/90	11/55	11/55	11/55	11/55	35.7/90	
CAPACITY (MBH)	40.2	40.4	40.6	40.8	57.2	268.1			266.7	238.8	26.5	181.1	95.5	135.2	198.4	56.6	134.5	297	297	297	531/90	54.6	303.02	194.8	301.9	54.5			
MAX. P.D. (ft. H ₂ O)	0.06	0.07	0.07	0.07	0.23	1.54			0.23	1.24	0.2	0.92	0.40	0.55	0.24	0.59	0.24	0.24	0.24	0.24	1.32	0.11	1.41	0.50	0.84	0.51			
WATER FLOW (gpm)	2.69	2.78	2.72	2.74	10	17.9			25.86	15.4	1.9	9.0	3.8	9.0	3.8	4.8	4.8	4.8	4.8	4.8	9.0	3.64	48	15	15	3.6			
EWT/LWT (F.)	180/150	180/150	180/150	180/150	180/150	180/150			180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150	180/150		
ROWS/FINS	1/80	1/89	1/89	1/89	2/5	1/11			1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80	1/80		
MODIFICATIONS	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)			NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	NEW (7)	


REMARKS: SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

- ① INVERTER DUTY MOTOR, FACTORY MOUNTED VFD.
- ② MODIFY FAN AS NECESSARY TO ACHIEVE NEW CFM AND STATIC PRESSURE REQUIREMENTS.
- ③ FOULING FACTOR 0.00025 FT²-F/BTU
- ④ WATER AND AIRFLOW FOR EACH AHU TO BE REBALANCED TO MATCH NEW CONDITIONS AS INDICATED BY THIS SCHEDULE FOR ALL EXISTING UNITS.
- ⑤ CONTRACTOR TO VERIFY CORRECT ECONOMIZER OPERATION FOR ALL NEW AND EXISTING AHUs. IF OPERATION IS INCORRECT CONTRACTOR TO REPLACE ACTUATORS AND DAMPERS AS REQUIRED TO ENSURE PROPER OPERATION. * NOT REQUIRED
- ⑥ REMOVE EXISTING VARIABLE FREQUENCY DRIVE AND ASSOCIATED ISOLATION TRANSFORMERS AND PROVIDE NEW VFD WITH INPUT LINE REACTORS PER SPECIFICATIONS. INSTALL VFD WITHIN AHU CABINET.
- ⑦ SINGLE POINT ELECTRICAL CONNECTION TO BE PROVIDED BY VENDOR FOR ALL NEW AHUs.
- ⑧ NOTE ALL CHILLED WATER COILS TO BE SELECTED WITH 30% PROPYLENE GLYCOL.
- ⑨ EXISTING FACE-AND-BYPASS REHEAT COIL, AHU-22.
- ⑩ FULL FLOW HEATING COIL IN THE REHEAT POSITION.
- ⑪ EQUIPMENT SELECTIONS BASED ON 91° DB/77° WB SUMMER AMBIENT AND 11° WINTER AMBIENT AND 72° DB SUMMER SPACE SET POINT AND 68° DB WINTER SPACE SET POINT.
- ⑫ ALL EXISTING AHUs SHALL BE RETROFITTED WITH: (a) RUSKIN JA050, OSA AIRFLOW MONITOR SEE DETAIL 4, SHEET M502; (b) REPLACE MOTORIZED RELIEF DAMPER WITH BAROMETRIC RELIEF DAMPER BALANCED FOR 0.02" W.C. OPERATING STATIC, AND (c) CONTROL VALVES & ACTUATOR FOR COOLING AND HEATING COIL.
- ⑬ PROVIDE FIRE/SMOKE ISOLATION DAMPER PER NFPA 90A AT UNIT RETURN AND DISCHARGE.

DUCT MOUNTED REHEAT COILS	7	19	20	26
SERVICE	REHEAT	REHEAT	REHEAT	REHEAT
TYPE	REHEAT	REHEAT	REHEAT	REHEAT
AIR FLOW (cfm)	4820	4538	13220	8617
MIN. SQ. FT.	12.25	11.67	18.0	14.69
MAX. FACE VELOCITY (fpm)	400	400	500	500
E.A.D.B. (F.)	35	17	23	24
L.A.D.B. (F.)	49	49	49	49
WATER FLOW (gpm)	9.52	12.25	32.48	16.91
WATER TEMP. ENTERING (F.)	180	180	180	180
MAX. P.D. (ft. H ₂ O)	5.0	5.0	2.21	5.0
ROWS/FINS	1/80	1/80	1/100	1/80
MAX. AIR S.P. (in. H ₂ O)	0.25	0.25	0.25	0.25
EXISTING SUPPLY DUCT SIZE	42"x42"	40"x40"	54"x48"	47"x47"
REHEAT COIL SIZE (LxH)	42x42	40x42	54x48	47x45

REMARKS: REHEAT COILS TO BE MOUNTED IN EXISTING DUCT ABOVE ROOF. DUCT TRANSITIONS, INSULATION TO BE IN ACCORDANCE WITH SMACNA MEDIUM PRESSURE DUCT DESIGN AND IN ACCORDANCE WITH DUCT EXPOSED TO WEATHER. MATCH EXISTING WHERE APPLICABLE.

ELECTRIC DUCT HUMIDIFIER	1	2	3	4	16	18	22	23
AHU DESIGNATION	EDH-1	EDH-2	EDH-3	EDH-4	EDH-16	EDH-18	EDH-22	EDH-23
MANUFACTURER	DRI-STEEM	DRI-STEEM	DRI-STEEM	DRI-STEEM	DRI-STEEM	DRI-STEEM	DRI-STEEM	DRI-STEEM
TYPE	ELECTRIC	ELECTRIC	ELECTRIC	ELECTRIC	ELECTRIC	ELECTRIC	ELECTRIC	ELECTRIC
MODEL	VLC 6-1	VLC 6-1	VLC 6-1	VLC 6-1	VLC 6-1	VLC 9-1	VLC 6-1	VLC 6-1
E.T. DB. (F.)/W.R.H.	49°/40%	49°/40%	49°/40%	49°/40%	49°/40%	49°/40%	49°/40%	49°/40%
HUMIDIFIED AREA	12x9	12x9	12x9	12x9	24x21	26x20	20x15	12x9
L.A.T. DB. (F.)/W.R.H.	49°/77%	49°/77%	49°/77%	49°/				




Date	Description	Symbol	Date	Description

Checked by: WIT	Date: 02/27/04
Drawn by: ICT	CADD File Name: 312.MIBS.DGN
DACAB7-03-D-0006	ICT Project No. 203121
Approved by: [Signature]	Plot date: 02/27/04
Chief, Proj. Mgmt. Division	Plot scale:


DEFENSE INFORMATION SCHOOL MARYLAND
 FT. MEADE
 CHILLED WATER FLOW SCHEMATIC DIAGRAM

Sheet reference number:
M-108



- NOTE(S):
- REBALANCE EXISTING HOT WATER REHEAT COIL FLOW TO INDICATED REQUIREMENTS.
 - NEW HWS/R TO NEW DUCT HTG. COIL OR NEW VAV BOX. BALANCE REHEAT COIL TO INDICATED REQUIREMENTS.
 - NEW HOT WATER SUPPLY & RETURN TO NEW AHU. NEW PIPE AND ROOF PENETRATION AT EACH COIL.
 - REFER TO DRAWING 611-620 FOR FLOOR PLAN DETAILS.
- INDICATES NEW VAV BOX OR AHU AND FLOW REQUIREMENTS.
 --- INDICATES EXISTING VAV BOX OR AHU

CW - FLOW SCHEMATIC - 2nd FLOOR PLAN
 NTS




THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I.C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITIES STATEMENT ON COVER SHEET.



NOTES:

- ① REMOVE EXISTING CONTROL VALVE V-2 AND ASSOCIATED PIPING AS INDICATED.
- ② REMOVE EXISTING TRIPLE-DUTY VALVE. SEE M-502 FOR REPLACEMENT COMPONENTS.



Date	Appr.	Symbol	Description

Date: 02/27/04	Checked by: WTT	Plot date: 02/27/04
CADD File Name: 312M202.DGN	Drawn by: ICT	Plot scale:
ICT Project No. 203121	DAC487-03-D-0006	Chief, P-1 Mgmt. Division

TASK ORDER #1 FRR004
 PADUCAH, KENTUCKY
 VOICE 270-442-8620
I.C. Thomasson
 REGISTERED PROFESSIONAL ENGINEER
 NASHVILLE, TENNESSEE
 PHONE (615) 248-3400



DEFENSE INFORMATION SCHOOL MARYLAND
MECHANICAL ROOM CHILLED WATER DEMOLITION

Sheet reference number:
M-202


LEGEND

	DEMO
	EXISTING
	EXTENT OF DEMOLITION

PARTIAL MECHANICAL ROOM CHW DEMOLITION



THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I.C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITY STATEMENT ON COVER SHEET.




Date	Description	Symbol	Date	Description

Checked by: WTT	Date: 02/27/04
Des by: ICT	CADD File Name: 312M204.DGN
DAC/07-03-D-0006	ICT Project No. 203121
Approved by: Chief, Proj. Mgmt. Division	Plot date: 02/27/04
Plot scale:	


TASK ORDER #1 FR0004
 PADUCAH, KENTUCKY
 VOICE 270-442-8620
 I.C. Thomasson
 Associates, Inc.
 NASHVILLE, TENNESSEE
 PHONE (615) 346-3400

DEFENSE INFORMATION SCHOOL MARYLAND
 FT. MEADE
 COURTYARD LTW DEMOLITION

Sheet reference number: M-204





THESE DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY OTHERS. I.C. THOMASSON HAS NOT VERIFIED THE ACCURACY AND /OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH MAY BE INCORPORATED HEREIN AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY OTHERS.






A B C D E F G H

6
5
4
3
2
1



- NOTE(S):
- ① REBALANCE EXISTING HOT WATER REHEAT COIL FLOW TO INDICATED REQUIREMENTS. SEE SCHEDULE.
 - ② NEW HWS/R TO NEW DUCT HTG. COIL OR NEW VAV BOX. BALANCE REHEAT COIL TO INDICATED REQUIREMENTS.
 - ③ NEW HOT WATER SUPPLY & RETURN TO NEW AHU. NEW PIPE AND ROOF PENETRATION AT EACH COIL.

ZONE No. 2 - 1st FLOOR HVAC PIPING






Symbol	Description	Date	Appr.

TASK ORDER #: FRR004
DATE: 02/27/04
ISSUED BY: WTT
DATE: 02/27/04
PROJECT NO.: 203121
PROJECT NAME: FT. MEADE CGN
PROJECT TITLE: ZONE 2 - 1st FLOOR HW PIPING
APPROVED BY: [Signature]
DATE: 02/27/04
DIVISION: Chief, Proj. Mgmt. Division

DEFENSE INFORMATION SCHOOL
 MARYLAND
 FT. MEADE
 ZONE 2 - 1st FLOOR
 HW PIPING


Sheet reference number:
M-612

THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I.C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITY STATEMENT ON COVER SHEET.




ZONE No. 4 - 2nd FLOOR HVAC PIPING

- NOTE(S):
- ① REBALANCE EXISTING HOT WATER REHEAT COIL FLOW TO INDICATED REQUIREMENTS.
 - ② NEW HWS/R TO NEW DUCT HTG. COIL OR NEW VAV BOX. BALANCE REHEAT COIL TO INDICATED REQUIREMENTS.
 - ③ NEW HOT WATER SUPPLY & RETURN TO NEW AHU. NEW PIPE AND ROOF PENETRATION AT EACH COIL.



NOTE(S):
 ① REBALANCE HW FLOW TO VAV REHEAT COIL. SEE SCHEDULE FOR REQUIREMENTS.



Date	Appr.	Symbol	Description



Date: 02/27/04	Checked by: MTT
CADD File Name: J21609.DGN	Drawn by: ICT
ICT Project No. 20321	DAC487-03-D-0006
Plot date: 02/27/04	Approved by: [Signature]
Plot scale:	Chief, Proj. Mgmt. Division

TASK ORDER # FFR004
 PADUCAH, KENTUCKY
 VOICE 270-442-8620
 I.C.T. THOMASSON
 10000 WOODBRIDGE BLVD
 WOODBRIDGE, KY 40390
 PHONE (603) 346-3400

DEFENSE INFORMATION SCHOOL
 FT. MEADE MARYLAND
 ZONE 4 - 2nd FLOOR
 HW PIPING

Sheet reference number:
M-619

THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I.C.T. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITIES STATEMENT ON COVER SHEET.



AHU CONTROLS
TYPICAL FOR VARIABLE AIR VOLUME UNITS
UNIT TYPE "D"

- ① HUMIDITY SENSORS SHALL BE DUCT MOUNTED WITHIN BUILDING A MINIMUM OF TWENTY FEET FROM PENETRATION.
- ② AHU-5, 6, 10, 11, 12, 13, 14, 15, 16, 17, 18, 21, 24, 27, 28 ARE UNIT TYPE "D"

SEQUENCE OF OPERATION
VARIABLE AIR VOLUME AIR-HANDLING UNIT

- SUPPLY AIR FAN (SAF):** THE SUPPLY AIR FAN VARIABLE FREQUENCY DRIVE (VFD) IS MANUALLY ENABLED WHEN THE H-O-A SWITCH IS IN THE HAND POSITION. IN THE AUTO POSITION, WHEN AIR IS REQUIRED FOR OPTIMUM START OR NIGHT SETBACK (HEATING OR COOLING) OR IF THE AIR-HANDLING UNIT IS SCHEDULED TO RUN, THE DDC CONTROLLER WILL ENABLE THE SUPPLY FAN VFD. WHEN AHU-6 AND AHU-21 ARE COMMANDED ON BY OR AUTOMATIC OR MANUAL INITIATION, THE DDC CONTROLLER SHALL OPEN SUPPLY AND RETURN FIRE/SMOKE DAMPERS AND CLOSE DAMPERS WHEN COMMANDED OFF. DAMPERS SHALL CLOSE IN ALARM CONDITION.
- FAN STATUS:** ALL FANS CONTROLLED BY VFDs WILL START AT A MINIMUM SPEED (CFM) AND STATUS SWITCHES WILL BE COORDINATED WITH THE MINIMUM FAN OUTPUT.

WHEN THE FAN IS TURNED ON, THE FAN STATUS DETERMINES IF THERE IS AIR MOVEMENT IN THE DUCT. AFTER AN OPERATOR-DEFINED FEEDBACK TIME DELAY, IF THERE IS NO AIR MOVEMENT IN THE DUCT, AN ALARM WILL BE GENERATED. ONCE THE TIME DELAY HAS PASSED, IF THE FAN STATUS INDICATES OFF (FIRE ALARM/FREEZESTAT, OVERLOADS, MANUAL SHUTDOWN) AND THE FAN IS COMMANDED ON, AN ALARM WILL BE GENERATED.
- RETURN AIR FAN (RAF):** THE RESPECTIVE RETURN AIR FAN VFD IS INTERLOCKED WITH THE SUPPLY FAN VFD TO BE ENABLED WHEN THE SUPPLY FAN VFD IS ENABLED. STATUS IS MONITORED TO GENERATE AN ALARM IF THE SUPPLY FAN VFD IS ENABLED BUT THE RETURN FAN STATUS INDICATES OFF AFTER THE PROOF FEEDBACK TIME DELAY HAS EXPIRED.
- MINIMUM OUTSIDE AIR DAMPERS:** THE MINIMUM OUTSIDE AIR DAMPERS WILL BE OPENED WHENEVER THE AIR-HANDLING UNIT IS SCHEDULED TO OPERATE. RETURN AIR TEMP IS MINIMUM 65°F, AND THE FAN STATUS INDICATES "ON". MINIMUM OUTSIDE AIR DAMPER SHALL MODULATE AS REQUIRED TO DELIVER SCHEDULED MINIMUM OSA BASED UPON MEASUREMENTS OF OUTSIDE AIRFLOW MEASURING STATION. WHEN OUTSIDE AMBIENT AIR TEMP. DROPS BELOW 40°F, FACE & BYPASS PREHEAT COIL VALVE SHALL OPEN TO ALLOW FULL FLOW OF HW THROUGH COIL. DAMPERS OF FACE & BYPASS PREHEAT COIL SHALL MODULATE AS REQUIRED TO MAINTAIN SCHEDULED DISCHARGE AIR TEMPERATURE OF AHU. WHEN THE AIR-HANDLING UNIT STARTS FOR OPTIMUM START OR NIGHT SETBACK, THE MINIMUM OUTSIDE AIR DAMPERS WILL REMAIN CLOSED.
- DISCHARGE AIR CONTROL:**
 - AIR TEMPERATURE CONTROL:** THE DDC CONTROLLER WILL MODULATE THE CHILLED WATER VALVE AS REQUIRED TO MAINTAIN THE SCHEDULED DISCHARGE AIR TEMPERATURE SETPOINT. SOFTWARE LOGIC WILL PREVENT SIMULTANEOUS HEATING AND COOLING. THE DISCHARGE AIR TEMPERATURE SENSOR WILL PREVENT DISCHARGE AIR TEMPERATURES FROM EXCEEDING LIMITS SET FOR PRE-HEAT MODE AND COOLING MODE. LIMITS FOR EACH MODE WILL BE OPERATOR DEFINED. MODE CHANGE FREQUENCY WILL BE OPERATOR DEFINED.
 - DISCHARGE TEMPERATURE RESET:** WHEN THE UNIT IS IN THE SCHEDULED UNOCCUPIED MODE, COOLING COIL VALVE SHALL MODULATE TO MAINTAIN A MAXIMUM DISCHARGE AIR TEMPERATURE OF 72°F WITH ALL ASSOCIATED VAV TERMINAL DEVICES INDEXED TO THE MINIMUM CFM POSITION. UPON A CALL FOR COOLING FROM ANY VAV ZONE (SPACE TEMP. GREATER THAN 85°F), THE DISCHARGE TEMP. SHALL RETURN TO SCHEDULED VALUE FOR 15 MINUTES AND THEN RETURN TO 72°F. WHEN THE UNIT RETURN AIR HUMIDITY SENSOR INDICATES RH GREATER THAN 58%, THE DISCHARGE AIR TEMP. SHALL RETURN TO THE SCHEDULED VALUE FOR 15 MINUTES AND THEN RETURN TO 72°F.
 - HUMIDIFICATION:** (UNITS AHU-16, 18)
THE DDC CONTROLLER WILL ENERGIZE HUMIDIFIER WHEN RETURN HUMIDITY SENSOR REPORTS RH BELOW 35%. THE CONTROLLER SHALL DEENERGIZE IF THE DISCHARGE HUMIDITY SENSOR INDICATES 95% RH OR GREATER.


- SUPPLY DUCT STATIC PRESSURE CONTROL:** THE DDC CONTROLLER WILL AUTOMATICALLY MODULATE THE SUPPLY FAN VFD WHEN THE VFD CONTROLLER SWITCH IS IN AUTOMATIC POSITION. SUPPLY FAN VFD WILL BE CONTROLLED MANUALLY WHEN THE VFD CONTROLLER SWITCH IS IN THE LOCAL POSITION. THE VFD WILL MODULATE BETWEEN THE MINIMUM AND MAXIMUM SPEED (CFM) SETTINGS TO MAINTAIN THE SUPPLY DUCT STATIC PRESSURE SETPOINT (INITIALLY SET AT 1.5" W.C., ADJUSTABLE).
- FAN TRACKING CONTROL:**
 - (FOR RETURN FAN CONTROL):** THE DDC CONTROLLER WILL AUTOMATICALLY MODULATE THE RETURN FAN VFD WHEN THE VFD CONTROLLER SWITCH IS IN THE AUTOMATIC POSITION. RETURN FAN VFD WILL BE CONTROLLED MANUALLY WHEN THE VFD CONTROLLER SWITCH IS IN THE LOCAL POSITION. THE VFD WILL MODULATE BETWEEN A MINIMUM AND MAXIMUM SPEED (CFM) TO MAINTAIN FAN TRACKING RELATIONSHIP WITH SUPPLY FAN AS INDICATED BELOW.

AHU	RETURN FAN SETTING AT SUPPLY FAN MAX. (CFM)	AHU	RETURN FAN SETTING AT SUPPLY FAN MAX. (CFM)
5	5164	16	4849
6	21821	17	9578
10	6999	18	5203
11	2970	21	15571
12	8221	24	21741
13	2004	27	8353
14	5399	28	12275
15	9015		

- (FOR EXHAUST FAN):** THE DDC CONTROLLER SHALL ENERGIZE THE ASSOCIATED EXHAUST FAN(S) ONLY WHEN MINIMUM OUTSIDE AIR DAMPER IS OPEN. SEE EXHAUST FAN INTERLOCK SCHEDULE.
- ECONOMIZER COOLING:** ECONOMIZER COOLING IS ENABLED WHENEVER THE OUTSIDE AIR ENTHALPY IS LESS THAN THE RETURN AIR ENTHALPY. WHEN THE ECONOMIZER IS ENABLED, THE DDC CONTROLLER WILL MODULATE IN CONCERT THE MAXIMUM OUTSIDE AIR DAMPER TO THE FULL OPEN POSITION AND THE RETURN AIR DAMPER TO THE FULL CLOSED POSITION AND THE COOLING COIL VALVE WILL MODULATE AS REQUIRED TO MAINTAIN THE DISCHARGE AIR TEMP. SETPOINT. AS OSA TEMP. DROPS, THE RETURN AIR AND MAX. OSA DAMPER SHALL MODULATE IN TANDEM (CLOSING MAX. OSA DAMPER) TO MAINTAIN SCHEDULED AHU DISCHARGE SETPOINT. WHEN MAX. OSA DAMPER CLOSES TO THE FULL CLOSED POSITION, THE PREHEAT SEQUENCE BEGINS.
- SAFETIES:** SAFETY DEVICES (DUCT SMOKE DETECTOR, FREEZESTAT, STATIC PRESSURE HIGH LIMIT) ARE INTERLOCKED WITH THE FAN STARTER CIRCUIT. THE DEVICES DISABLE THE SUPPLY FAN AND RETURN FAN VFDs, CLOSE THE MINIMUM AND MAXIMUM OSA DAMPERS, AND FULLY OPEN THE RETURN DAMPERS. ALL SAFETIES SHALL HAVE AUXILIARY CONTACTS SUCH THAT WHEN ACTIVATED THE DDC CONTROLLER WILL GENERATE AN ALARM. ANY FIRE ALARM SYSTEM SIGNAL GENERATED IN THE BUILDING SHALL CAUSE THE DDC SYSTEM TO SHUT DOWN ALL AHUS.
- PREHEAT COIL CONTROL:** THE DDC CONTROLLER WILL ENABLE THE IFB PREHEAT COIL HOT WATER VALVE WHENEVER THE OUTSIDE AIR TEMPERATURE IS BELOW 40°F. REGARDLESS OF WHETHER THE UNIT IS COMMANDED ON OR NOT, THE DDC CONTROLLER WILL MODULATE THE FACE AND BYPASS DAMPERS TO MAINTAIN SCHEDULED AHU DISCHARGE AIR TEMP.


PANEL DESIGNATION FT. MEADE - DINFOS	HARDWARE				SOFTWARE								
	OUTPUT (O)		INPUT (T,D,V,C)		ALARMS		PROGRAM						
	DIGITAL	ANALOG	DIGITAL	ANALOG	DIGITAL	ANALOG							
AHU CONTROLS VARIABLE AIR VOLUME AIR HANDLING UNIT UNIT TYPE "B"	Control Relay	Solenoid Contactor	Pneumatic Transducer	Electrical Transducer 4-20MA, Modulo	Differential Pressure Flow Switch	Pres. Switch Closure Open/Close	Temperature Relative Humidity	Pressure Position Flow	Equipment Status Maintenance	High Limit Low Limit Run Time	Scheduled Optimum Start/Stop Duty Cycling Demand Limiting Day/Night Setback Economizer Ventilation/Recirculation Temperature Control Humidity Control Supply Static Pressure Speed Control Position		
POINT DESCRIPTION													
SUPPLY AIR FAN S/S													
SUPPLY AIR FAN STATUS													
RETURN AIR FAN STATUS													
SUPPLY STATIC PRESSURE													
SUPPLY PRESSURE HIGH LIMIT													
SUPPLY FAN VFD													
RETURN FAN VFD													
SUPPLY AIRFLOW STATION													
RETURN AIRFLOW STATION													
RETURN AIR TEMPERATURE													
RETURN AIR HUMIDITY													
MIXED AIR TEMPERATURE													
UNIT DISCHARGE AIR TEMP.													
PREHEAT COIL AIR TEMPERATURE													
OUTSIDE AIR HUMIDITY													
OUTSIDE AIR TEMPERATURE													
MIN. OSA DAMPER CTL													
MAX. OSA DAMPER CTL													
RETURN AIR DAMPER CONTROL													
OUTSIDE AIRFLOW STATION													
FILTER (2 THUS)													
HOT WATER VALVE CONTROL													
CHILLED WATER VALVE CONTROL													
FACE & BYPASS DAMPER CTL													
F/S DAMPER CTL (AHU-6 & -21)													
HUMIDIFIER (AHU-6 & -21)													
HUMIDIFIER HIGH LIMIT (AHU-6&21)													
SUPPLY HUMIDITY (AHU-6&21)													
DUCT SMOKE DETECTOR													
FREEZESTAT													

NOTE: PROVIDE DYNAMIC GRAPHIC REPRESENTATIVE OF EACH PIECE OF EQUIPMENT




SUPPLY FAN VFD

RETURN FAN VFD



SUPPLY FAN CONTROL



RETURN FAN CONTROL



Checked by: WT
DIN by: ICT
PAULCH, KENTUCKY
VOICE 270-442-8620
J.C. THOMASSON, INC.
NASHVILLE, TENNESSEE
PHONE (615) 346-3400

Task Order #: FFR004
DIN File Name: 312.MB03.DGN
ICT Project No.: 203121
Date: 02/27/04
Plot date: 02/27/04
Plot scale:

DEFENSE INFORMATION SCHOOL
MARYLAND
FT. MEADE
NEW VARIABLE VOLUME
AHU CONTROLS

Sheet reference number:
M-806

THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I. C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITIES STATEMENT ON COVER SHEET.

