


DDC CONTROL POINT SCHEDULE


PANEL DESIGNATION CHILLED WATER, CONDENSER WATER, & ICE BUILDING FT. MEADE, DINFOS	INPUTS		OUTPUTS		SYSTEM FEATURES					
	ANALOG		DIGITAL	DIGITAL	ALARMS	PROGRAMS				
	MEASURED	CALC.								
	TEMPERATURE PRESSURE RH AIR FLOW AIR QUALITY KW WATER FLOW VOLTAGE STEAM FLOW lbs./hr. ICE LEVEL KWH ENTHALPY RUN TIME EFFICIENCY STS. CAP.(TONS) BACKUP INTERFACE		STATUS FILTER SMOKE LOW TEMP. AIR FLOW METER CURRENT SWITCH FIRE ALARM PRESSURE ON-OFF OFF-AUTO-ON OFF-HIGH-LOW OPEN-CLOSE 2-POSITION VALVES	DAMPER POSI. VALVE POSI. SET POINT ADJ. 4-20 mA	ANALOG H ANALOG H BINARY L BINARY BINARY PROOF	TIME SCHEDULING DEMAND LIMITING START/STOP OPTIM. SPEED CONTROL HOT WATER RESET ALARM INSTRUCTION LEAD/LAG CONTROL ICE BUILDING				
CHILLERS:										
CH-1 W/GATEWAY	X					X				
CH-2 W/GATEWAY	X					X				
CH-3 W/GATEWAY	X					X				
CH-4 W/GATEWAY	X					X				
CH-1 START/STOP									X	
CH-2 START/STOP									X	
CH-3 START/STOP									X	
CH-4 START/STOP									X	
CHILLED WATER SYSTEM:										
PRIMARY PUMP P-1 START/STOP						X				
PRIMARY PUMP P-2 START/STOP						X				
PRIMARY PUMP P-3 START/STOP						X				
PRIMARY PUMP P-11 START/STOP						X				
PRIMARY PUMP P-12 START/STOP						X				
PRIMARY PUMP P-1 STATUS										X
PRIMARY PUMP P-2 STATUS										X
PRIMARY PUMP P-3 STATUS										X
PRIMARY PUMP P-11 STATUS										X
SECONDARY PUMP P-7 VFD						X				
SECONDARY PUMP P-8 VFD						X				
SECONDARY PUMP P-7 STATUS										X
SECONDARY PUMP P-8 STATUS										X
CHILLED WTR DIFF. PRESS. (1 LOCATION)	X									
SECONDARY CHWR TEMP. (SYS)	X									
SECONDARY CHWS TEMP. (SYS)	X									
ENTERING THERMAL STOR. RETURN WATER TEMP.	X									
LEAVING THERMAL STOR. SUPPLY WATER TEMP.	X									
ENTERING WATER TEMP. (CH-1)	X									
LEAVING WATER TEMP. (CH-1)	X									
ENTERING WATER TEMP. (CH-2)	X									
LEAVING WATER TEMP. (CH-2)	X									
ENTERING WATER TEMP. (CH-3)	X									
LEAVING WATER TEMP. (CH-3)	X									
ENTERING WATER TEMP. (CH-4)	X									
LEAVING WATER TEMP. (CH-4)	X									
PRIMARY CHILLED WTR TEMP.	X									
DECOUPLE CHILLED WTR TEMP.	X									
SECONDARY CHILLED WTR FLOW	X									
PRIMARY LOOP CHILLED WTR TONS		X			X					
ISOLATION VALVE V-10						X				
TEMP. CONTROL VALVE V-14							X	X		
CALMAC ICE LEVEL INDICATOR		X								X
ISOLATION VALVE V-12, V-13						X				X
CONDENSER WATER SYSTEM:										
COND. WTR. PUMP P-4 START/STOP						X				
COND. WTR. PUMP P-5 START/STOP						X				
COND. WTR. PUMP P-6 START/STOP						X				
CONDENSER WTR. PUMP P-4 STATUS										X
CONDENSER WTR. PUMP P-5 STATUS										X
CONDENSER WTR. PUMP P-6 STATUS										X
ENTERING COND. WTR. TEMP. (CH-1, -2, -3)	X									
LEAVING COND. WTR. TEMP. (CH-1, -2, -3)	X									
CT-1 - TWO SPEED						X		X		X
CT-2 - TWO SPEED						X		X		X
CT-3 - TWO SPEED						X		X		X
COND WATER BYPASS VALVE V-20										
ISOLATION VALVE V-21, V-22, V-23						X				

NOTE: PROVIDE DYNAMIC GRAPHIC REPRESENTATIVE OF EACH PIECE OF EQUIPMENT.



EXISTING ANDOVER ENERGY MANAGEMENT SYSTEM NETWORK WIRING SCHEMATIC

- EXISTING ANDOVER CONTROL SYSTEM:
- REUSE AS MUCH OF THE EXISTING SYSTEM AS POSSIBLE.
 - ALL VALVE AND DAMPER ACTUATORS SERVING NEW AND EXISTING ROOF MOUNTED AHUS SHALL BE ALL ELECTRIC. CAP EXISTING PNEUMATIC LINES WHERE APPLICABLE.
 - EXISTING VALVE ACUTATORS LOCATED IN MAIN MECHANICAL ROOM UNTOUCHED BY THIS UPGRADE SHALL REMAIN PNEUMATIC.



TYPICAL NEW & EXISTING VARIABLE VOLUME REHEAT BOX CONTROL

- NOTES:
- EXISTING BOXES SHALL HAVE VAV DISCHARGE TEMPERATURE SENSOR ADDED (ALL OTHER DEVICES ARE EXISTING).
 - SEE VAV SCHEDULE FOR MAXIMUM DISCHARGE AIR TEMPERATURES.

TYPICAL VARIABLE VOLUME

SEQUENCE OF OPERATION

- BOX STATUS (OCCUPIED/UNOCCUPIED): THE VARIABLE AIR VOLUME REHEAT BOX WILL HAVE TWO STATES OF OPERATION. DURING THE OCCUPIED MODE WHEN THE DEVICE IS SCHEDULED OR IN THE UNOCCUPIED MODE WHEN THE DEVICE IS SCHEDULED FOR OPTIMUM START OR NIGHT SETBACK (HEATING OR COOLING), IN EITHER CASE, THE DAMPER AND HOT WATER VALVE WILL BE ENABLED TO MAINTAIN THE SPACE TEMPERATURE SETPOINT. DURING THE UNOCCUPIED PERIODS, THE DAMPER WILL REMAIN AT THE MINIMUM (CFM) POSITION AND THE HOT WATER VALVE WILL REMAIN CLOSED EXCEPT TO SATISFY NIGHT SETBACK SETPOINTS OF 85°F LAT (ADJUSTABLE) FROM APRIL TO SEPTEMBER AND 55°F LAT (ADJUSTABLE) FROM OCTOBER TO MARCH.
- DAMPER MODULATION: DURING THE OCCUPIED STATE, THE DDC CONTROLLER WILL MODULATE THE AIR VOLUME DAMPER BETWEEN MAXIMUM (CFM) AND MINIMUM (CFM) AIRFLOW. ON A RISE IN SPACE TEMPERATURE, AIRFLOW IS INCREASED FROM MINIMUM TO MAXIMUM. ON A DECREASE IN TEMPERATURE, AIRFLOW IS DECREASED FROM MAXIMUM TO MINIMUM.
- REHEAT VALVE MODULATION: DURING THE OCCUPIED STATE, THE DDC CONTROLLER WILL MODULATE THE HOT WATER CONTROL VALVE BETWEEN FULLY OPEN AND CLOSED POSITION. ON A RISE IN TEMPERATURE, THE HOT WATER VALVE MODULATES FROM FULLY OPEN TO CLOSED AND SEQUENTIAL DAMPER MODULATION BEGINS. ON A DROP IN SPACE TEMPERATURE, ONCE THE AIR DAMPER IS AT A MINIMUM (CFM) POSITION, THE DDC CONTROLLER WILL MODULATE THE HOT WATER VALVE FROM CLOSED TO FULLY OPEN.
- HEATING AND COOLING REQUESTS: ANY VARIABLE AIR VOLUME BOX MAY INITIATE A REQUEST TO ITS RESPECTIVE AIR HANDLING UNIT FOR HEATING OR COOLING DURING THE UNOCCUPIED STATE. WHEN AIR IS REQUIRED FOR OPTIMUM START OR NIGHT SETBACK (HEATING OR COOLING), THE AIR HANDLING UNIT WILL START TO SATISFY THE ZONE SERVED BY THE VARIABLE AIR VOLUME BOX. IN ADDITION, EACH DEVICE WILL BE ABLE TO REQUEST THE RESPECTIVE HEAT SOURCE (HOT WATER PUMPS/BOILER) DURING THIS UNOCCUPIED STATE.

PANEL DESIGNATION FT. MEADE, DINFOS	HARDWARE						SOFTWARE										
	OUTPUT (O)			INPUT (T,D,V,C)			ALARMS		HARDWARE								
	DIGITAL	ANALOG	DIGITAL	ANALOG	DIGITAL	ANALOG	DIGITAL	ANALOG	SCHEDULED START/STOP	DAY/COOL START/STOP	DEMAND LIMITING	MIN/NIGHT SETBACK	ECONOMIZER	TEMPERATURE SCHEDULE	HOT WATER RESET	CHILDR OPTIMIZATION	CHILDR WATER RESET
LOCATION:																	
VAV BOX CONTROLS																	
POINT DESCRIPTION																	
ZONE TEMPERATURE																	
VAV DISCHARGE TEMP.																	
FLOW (CFM)																	
CONTROL OUTPUT-DAMPER																	
CONTROL OUTPUT-VALVE																	
UNIT ENABLE/DISABLE																	
UNIT STATUS																	

NOTE: PROVIDE DYNAMIC GRAPHIC REPRESENTATIVE OF EACH PIECE OF EQUIPMENT


INTERLOCK SCHEDULE

ENERGIZE EXHAUST FAN	SERVING	WHEN AHU MIN. OSA DAMPER(S) ARE OPEN ON AHU(S)
EF-1A	TOILETS (1108-1110) & (2104-2106)	AHU-6 & AHU-26
EF-1B	TOILETS (1136-1138) & (2142-2144)	AHU-6 & AHU-26
EF-1C	TOILETS (1206-1208) & (2226-2228)	AHU-10 & AHU-19
EF-1D	TOILETS (1166-1168) & (2166-2168)	AHU-21 & AHU-20
EF-2	TOILET 1163	AHU-28
EF-3A	EQUIPMENT ROOM 1165	AHU-21
EF-3B	EQUIPMENT ROOM 1112	AHU-6
EF-3C	EQUIPMENT ROOM 1216	AHU-9
EF-8A	VERSAMAT 1148	AHU-15
EF-8B	VERSAMAT 1146	AHU-15
EF-9	APPLIED IMAGERY	AHU-15
EF-10	COLOR PRINTING (1175, 1177A,B,C, & D, & 1172)	AHU-21
EF-11	AUTOMATIC COLOR FINISHING (1178, 1186)	AHU-14
EF-12	B & W PRINT FINISHING (1179A, 1188, 1190)	AHU-13 & AHU-14
EF-13	B & W PRINTING AUTOMATIC (1194, 1196)	AHU-13
EF-14	CORRIDOR 1197	AHU-10
EF-15	PROCESSING LAB (1185, 1187, 1189, 1191, 1193)	AHU-12
EF-16	LOGISTICS SUPPLY & PHOTO EQUIPT MAINT (1205, 1212C)	AHU-10
EF-17	MACHINE SHOP (1201) & PROCESS MAINT LAB (1198, 1199)	AHU-10 & AHU-29
EF-18	DEMO WORKSTATIONS (2196, 2197) & TRANS. LAB (2205)	AHU-19 & AHU-20

- LEGEND
- ▲ LOCATE PILOT LGT IN STARTER COVER
 - ▲▲ LOCATE PILOT LGT IN LOCAL CONTROL PANEL
 - AO ANALOG OUTPUT
 - AI ANALOG INPUT
 - DO DIGITAL OUTPUT
 - DI DIGITAL INPUT
 - NO NORMALLY OPEN
 - NC NORMALLY CLOSED



THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. J.C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITY STATEMENT ON COVER SHEET.



Date	Appr.	Description

Checked by: WTT Date: 02/27/04
 Den by: ICT CAD File Name: 270-442-8620
 D:\CAB7-03-D-0008 ICT Project No. 20321
 Approved by: Per date: 02/27/04
 Chief, Prj. Mgmt. Division Plot scale:

TASK ORDER # FFR004
 RAULICH, KENTUCKY
 VOICE 270-442-8620
 J.C. Thomason, Inc.
 Huntsville, TN
 PHONE (615) 346-3400

DEFENSE INFORMATION SCHOOL MARYLAND
 FT. MEADE
 VAV CONTROLS

Sheet reference number:
M-800