




**COMBUSTION VENTILATION FAN CONTROL DETAIL**  
NO \_\_\_\_\_ SCALE



**COMBUSTION SUPPLY FAN CONTROL DETAIL**  
NO \_\_\_\_\_ SCALE




**CSF TEMPERATURE CONTROL DIAGRAM**




**BOILER CONTROLS**

NOTE: PROOF OF FLOW OF HWP-1 OR HWP-2 SHALL BE ESTABLISHED AND RESPECTIVE BP-1 OR BP-2 SHALL RUN 2 MINUTES (ADJUSTABLE) BEFORE DDC CONTROLLER ENERGIZES BOILER B-1 OR B-2.



**BOILER RECIRCULATING PUMP CONTROLS**

NOTE: PUMP BP-1 SHALL RUN TWO MINUTES BEFORE B-1 IS ENERGIZED AND SHALL RUN FOR THIRTY MINUTES AFTER B-1 IS DE-ENERGIZED. BP-2 AND B-2 SIMILAR.



**HOT WATER PUMP VFD**

PANEL DESIGNATION FT. MEADE DINFOS	HARDWARE						SOFTWARE					
	OUTPUT (O)			INPUT (I, D, V, C)			ALARMS		HARDWARE/SOFTWARE			
	DIGITAL	ANALOG	RELAY	DIGITAL	ANALOG	DIGITAL	ANALOG					
LOCATION: MAIN MECHANICAL ROOM												
POINT DESCRIPTION	Control Relay	Relay	Relay	Temperature Sensor	Temperature Sensor	Temperature Sensor	Pressure Switch	Pressure Switch	Pressure Switch	Pressure Switch	Pressure Switch	Pressure Switch
BOILER NO. 1 S/S												
BOILER NO. 2 S/S												
BP-1												
BP-2												
HOT WTR PUMP P-9 VFD												
HOT WTR PUMP P-10 VFD												
HWS TEMP CTRL V-1												
ISOLATION VALVE V-2												
ISOLATION VALVE V-3												
COMBUSTION VENT FAN CVF-1												
COMBUSTION SUPPLY FAN CSF												
COMBUSTION SUPPLY AIR												
HOT WATER VALVE												
SECONDARY HWS TEMP SENSOR												
SECONDARY HWR TEMP SENSOR												
HWS TEMP B-1												
HWR TEMP B-1												
HWS TEMP B-2												
HWR TEMP B-2												
HWS TEMP B-2												
HWR TEMP B-2												
HW LOOP PRESSURE												
OUTSIDE AIR TEMP												
EXIST. REFRIG. SENSOR												

**SEQUENCE OF OPERATION BOILERS & HOT WATER PUMPS**

- THE BUILDING IS SERVED BY TWO HEATING WATER BOILERS B-1 AND B-2. BOILERS ARE CONTROLLED BY UNIT-MOUNTED, FACTORY-FURNISHED DDC MICROPROCESSORS, WITH A GATEWAY TO THE EXISTING ANDOVER DDC SYSTEM TO COMMUNICATE STATUS AND ALARMS AND ISSUE BOILER START/STOP. HOT WATER SYSTEM TO RUN CONTINUOUSLY TO SATISFY BUILDING HEATING LOAD AND VAV REHEAT COIL PERFORMANCE AND TO CONTROL HUMIDITY AS REQUIRED AT CONSTANT VOLUME AHU REHEAT HUMIDITY CONTROL.
- HOT WATER PUMPS P-9 AND P-10 ARE ENERGIZED THROUGH ACTION OF H-O-A LOCATED IN STARTER. MANUAL START WHEN IN HAND POSITION OR BY DDC CONTROLLER WHEN IN AUTO POSITION. AFTER ENERGIZED, PUMPS SHALL START IN THE MINIMUM SPEED POSITION. PUMP SPEED SHALL RAMP UP OR DOWN AS REQUIRED VIA DDC CONTROL SIGNAL TO PUMP VFD TO MAINTAIN DIFFERENTIAL PRESSURE (INITIALLY SET AT 6 PSI) MEASURED APPROXIMATELY TWO-THIRDS ALONG HEATING WATER SUPPLY AND RETURN MAIN HEADER.
- AFTER PROOF OF FLOW OF P-9 OR P-10 AS DETERMINED BY PUMP DIFFERENTIAL PRESSURE SWITCH IS ESTABLISHED, BOILERS B-1 AND B-2 MAY BE ENERGIZED THROUGH ACTION OF UNIT MOUNTED H-O-A SWITCH. BOILERS MAY BE STARTED MANUALLY WHEN IN THE HAND POSITION OR BY DDC WHEN IN AUTO POSITION.
  - RESPECTIVE RECIRCULATING PUMPS BP-1 (FOR BOILER B-1) AND BP-2 (FOR BOILER B-2) SHALL BE ENERGIZED WHEN RESPECTIVE BOILER IS ENERGIZED. RECIRCULATING PUMPS SHALL BE STARTED AND RUN FOR TWO MINUTES BEFORE BOILER IS ENERGIZED AND SHALL CONTINUE TO RUN FOR THIRTY MINUTES AFTER BOILER IS DE-ENERGIZED. COMBUSTION VENTILATION FAN CVF IS ENABLED WHEN EITHER BOILER B-1 OR B-2 IS ENERGIZED. WHEN BOILER IS ENERGIZED AND BOILER DISCHARGE TEMPERATURE SETPOINT IS ACHIEVED, ASSOCIATED ISOLATION VALVE (V2 OR V3) SHALL OPEN AND REMAIN OPEN UNTIL BOILER IS DE-ENERGIZED BY THE DDC SYSTEM.
  - ON A CALL FOR HEAT FROM LEAD/LAG BOILER, CVF-1 CONTROLS SHALL BE ENABLED. STACK PRESSURE PROBE SHALL SIGNAL THAT PRESSURE DIFFERENTIAL REQUIREMENT IN STACK HAS CHANGED AND CONTROLLER WILL ENABLE CVF-1 VFD TO RAMP UP FAN SPEED TO MEET DIFFERENTIAL REQUIREMENT. ONCE DIFFERENTIAL REQUIREMENT IS MET, CVF-1 CONTROLLER SHALL ENABLE LEAD/LAG BOILER BURNER. IF AT ANYTIME THERE IS FAILURE TO ESTABLISH DIFFERENTIAL PRESSURE REQUIREMENT (40% BELOW SETPOINT FOR MORE THAN 12 SECONDS), CVF-1 CONTROLLER SHALL DISABLE BOILERS AND GENERATE AN ALARM AT THE BAS. CVF-1 SHALL CONTINUE TO RUN FOR 3 MINUTES AFTER BOILERS ARE DE-ENERGIZED.
  - ON A CALL FOR HEAT FROM LEAD/LAG BOILER OR WATER HEATER, CSF-1 CONTROLS SHALL BE ENABLED. CSF-1 CONTROLLER SHALL MONITOR MECHANICAL ROOM PRESSURE COMPARED TO OUTDOOR PRESSURE AND RAMP VFD FOR CSF-1 UP OR DOWN AS REQUIRED TO MAINTAIN POSSITIVE PRESSURE CONDITION IN MECHANICAL ROOM. IF ROOM PRESSURE DROPS BELOW ESTABLISHED SETPOINT, CSF-1 CONTROLLER SHALL SHUT-DOWN WATER HEATER AND BOILERS AS REQUIRED AND ALARM THE DDC SYSTEM. HOT WATER HEATING VALVE FOR HC-1 (CSF-1) SHALL MODULATE OPEN TO CLOSED AS REQUIRED TO MAINTAIN A MINIMUM OF 50°F DISCHARGE TEMPERATURE.
- LEAD/LAG CONTROL OF BOILERS AND HOT WATER PUMPS IS ACCOMPLISHED BY THE DDC SYSTEM. WHEN LEAD BOILER IS AT FULL FIRING AND HW LOOP IS 5°F BELOW SETPOINT FOR 20 MINUTES, DDC CONTROLLER SHALL ENERGIZE LAG BOILER. INTEGRAL BOILER CONTROL SHALL ENSURE EQUAL LOADING OF BOILERS. IF AFTER 20 MINUTES BOTH BOILERS ARE AT LESS THAN 50% FIRING, AND LOOP SETPOINT TEMPERATURE IS SATISFIED, DDC SYSTEM SHALL SHUT DOWN LAG BOILER. IF AFTER 10 MINUTES, LEAD PUMP CANNOT SATISFY LOOP DIFFERENTIAL PRESSURE SETPOINT (6 PSI ADJUSTABLE), DDC SYSTEM SHALL START LAG PUMP IN THE MINIMUM SPEED POSITION. OPTIMIZATION PROGRAM SHALL ENSURE EQUAL LOADING OF PUMPS. WHEN AFTER 10 MINUTES, BOTH PUMPS ARE OPERATING AT 23 HZ OR LESS (ADJUSTABLE) AND LOOP DIFFERENTIAL PRESSURE SETPOINT IS SATISFIED, DDC SHALL SHUT DOWN LAG PUMP.
- TEMPERATURE CONTROL MIXING VALVE (V-1) TO MODULATE TO MAINTAIN HOT WATER TEMPERATURE IN HW LOOP AS INDICATED BY TEMPERATURE RESET SCHEDULE. TEMPERATURE CONTROL MIXING MODULATION SHALL BE LIMITED SUCH THAT BOILER ENTERING WATER TEMPERATURE DOES NOT FALL BELOW 150°F.
- COMBUSTION SUPPLY FAN (CSF) SHALL RUN CONTINUOUSLY.
- AN ALARM SHALL BE GENERATED AT THE CENTRAL CONTROL STATION IF BOILER ENTERING WATER TEMPERATURE IS BELOW 140°F OR BOILER LEAVING WATER TEMPERATURE EXCEEDS 205°F (ADJUSTABLE) OR A STATUS ALARM GENERATED BY INTEGRAL DDC BOILER CONTROL PANEL IS PASSED TO THE EXISTING CENTRAL ANDOVER SYSTEM.
- UPON ACTIVATION OF MACHINERY ROOM REFRIGERANT LEAK DETECTION, THE DDC SYSTEM SHALL SHUT-DOWN BOILERS B-1 AND B-2.

**HOT WATER TEMPERATURE RESET SCHEDULE**

O.A. TEMP.	HOT WATER TEMP.
≥ 70°	170°F
< 70°	200°F

THESE DOCUMENTS HAVE BEEN PREPARED PRIMARILY BASED ON INFORMATION PROVIDED BY OTHERS. I.C. THOMASSON HAS NOT VERIFIED THE ACCURACY OF ALL INFORMATION PROVIDED BY OTHERS. SEE LIMIT OF LIABILITIES STATEMENT ON COVER SHEET.

Rev.	Date	Appr.	Description

Checked by: WT  
 Dwg. by: ICT  
 Date: 02/27/04  
 CAD File Name: 312M804.DGN  
 I.C. Thomasson, Inc.  
 Nashville, Tennessee  
 Phone: (615) 346-3400

**ICIT**

DEFENSE INFORMATION SCHOOL MARYLAND  
 FT. MEADE  
 BOILER CONTROLS

Sheet reference number:  
**M-802**