BRACED WALL PLAN CONSTRUCTION

7/16" ZIP WALL WOOD STRUCTRUAL PANEL SHEATHING ATTACHED TO FRAMING WITH 6d AT 6" OC AT PANEL EDGES, AND 12" OC AT INTERMEDIATE MEMBERS
2X6 WALL STUDS TO BE AT 16" OC WITH 1/3 HEIGHT BLOCKING DOUBLE 2X6 TOP PLATE W/ OVERLAPING CORNERS AND SINGLE BOTTOM PLATE
MIN. R21 FIBERGLASS BATT INSULATION BETWEEN ALL STUD BAYS ALL TOP AND BOTTOM PLATE PENETRATIONS TO BE FIRE STOPPED
GYPSUM WALL BOARD TO BE APPLIED TO INTERIOR OF FRAMING WITH ADHESIVE AND TYPE S OR W SCREWS @ 7" OC AT PANEL EDGES AND 24" OC AT INTERMEDIATE FRAMING MEMBERS

EXTERIOR WALLS TO BE OF 2x6 AT 16" OC W/ 1/3 HEIGHT BLOCKING W/ DOUBLE TOP PLATE
INTERIOR BEARING WALLS TO BE MIN. 2x6 AT 16" OC W/ 1/3 HEIGHT BLOCKING W/ DOUBLE TOP PLATE
INTERIOR NON BEARING WALLS TO BE 2x6 AT 16" OC W/ DOUBLE TOP PLATE

TYP. WINDOW AND DOOR HEADER POST SCHEDULE
1-2x6 (1-KING STUD, 1- JACK STUD)
2- 2x6 (1- KING STUD, 2- JACK STUDS)
3- 2x6 (1- KING STUD, 3- JACK STUDS)

WALL BRACING DESIGN INFO

LOCATION: HARFORD COUNTY, MARYLAND
SEISMIC CATEGORY: B
WIND SPEED: 115 MPH

METHOD 3 (WOOD SHEATHING) / CONTINOUS SHEATHING
METHOD 5 (GYPSUM BOARD)

*THESES DRAWINGS ARE LIMITED TO IRC WALL BRACING REQUIRMENTS ONLY

LEDGEND

CS-WSP CONTINUOUS SHEATHING- WOOD STRUCTRUAL PANEL (-LENGTH)
CS-PF CONTINOUS SHEATHED PORTIAL FRAME
ABW ALTERNATE BRACED WALL
GB-1 36" (1 SIDE)
GB-2 48" (2 SIDES)
TIE DOWN DEVICE (- LBS)

R602.10.4 CONTINOUS SHEATHING. BRACED WALL LINES WITH CONTINOUS SHEATHING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THIS SECTION. ALL BRACED WALL LINES ALONG EXTERIOR WALLS ON THE SAME STORY SHALL BE CONTINOUSLY SHEATHED.



1 GABLE END WALL BRACE
SCALE: 1/4"=1'-0"


BRACED WALL LINE 1
BRACED WALL LINE 2
BRACED WALL LINE 3
BRACED WALL LINE F
BRACED WALL LINE B
BRACED WALL LINE A
BRACED WALL LINE J
BRACED WALL LINE L
BRACED WALL LINE K
BRACED WALL LINE I
BRACED WALL LINE 6
BRACED WALL LINE 8
BRACED WALL LINE 10
BRACED WALL LINE H
BRACED WALL LINE G
BRACED WALL LINE E
BRACED WALL LINE D
BRACED WALL LINE C
BRACED WALL LINE 5
17'-0"
8'-6"
2x8 SUBFASCIA BOARD
HIP GIRDER TRUSS
3 PLY 1-3/4" x 11-7/8" LVL HDR.
16'-0"
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
T.P.I APPROVED HIP MONO TRUSSES AT 24" OC SPACING
T.P.I APPROVED ROOF MONO TRUSSES AT 24" OC SPACING
T.P.I APPROVED ROOF TRUSSES AT 24" OC SPACING
T.P.I APPROVED OVERBUILD ROOF TRUSSES AT 24" OC SPACING
BEDROOM #3
12'-4" CLG.
BREEZEWAY
ROOF GIRDER TRUSS
MUDROOM
12'-4" CLG.
BEDROOM #2
12'-4" CLG.
CURBLESS TILE SHOWER
BATHROOM
10' CLG.
KITCHEN
12' 4" CLG.
3 PLY 1-3/4" x 14" FLUSH LVL
14" 60 SERIES I JOIST AT 16" OC SPACING
T.P.I APPROVED ROOF TRUSSES AT 24" OC SPACING
2 PLY 1-3/4" x 14" LVL
W.I.C
PANTRY
HALF BATH
STORAGE
ATTIC GIRDER TRUSS
UP TO ATTIC FLOOR 2 RISERS AT 7-3/4" 20 TREADS AT 10" RUN
2 CAR GARAGE
18' x 8' GARAGE DOOR
T.P.I APPROVED ROOF MONO TRUSSES AT 24" OC SPACING
CORNER JACK GIRDER TRUSS
T.P.I APPROVED ATTIC ROOF TRUSSES AT 24" OC SPACING
W8 x 21 STEEL BEAM FOR STONE SUPPORT
3" SCHED COL.
P.T. 8x8 SUPPORT POST ON ABA88 BASE ATTACH BEAM TO NOTCHED POST WITH 4 7" STRUCTURAL SCREWS TYP. OF 8
5.5 x 5.5 PSL POST
SCREEN PORCH
FOYER
14' 4" CLG.
DESK NOOK
OWNER BATH
12' 4" CLG.
LAUNDRY
12' 4" CLG.
COVERED PORCH
FAMILY ROOM
16' 4" CLG.
OWNER SUITE
15' 4" CLG.
BREAKFAST NOOK
12'4" CLG.
FLAT GIRDER TRUSS
ROOF GIRDER TRUSS
3 PLY 1-3/4" x 16" DROPPED LVL
3 PLY 1-3/4" x 9-1/4" LVL HDR.
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
3 PLY 1-3/4" x 14" FLUSH LVL
3 PLY 1-3/4" x 24" FLUSH LVL
2 PLY 1-3/4" x 14" FLUSH LVL
2 PLY 1-3/4" x 14" LVL
2 PLY 1-3/4" x 14" FLUSH LVL
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
3 PLY 1-3/4" x 11-7/8" LVL HDR.
3 PLY 1-3/4" x 9-1/4" LVL HDR.
3 PLY 1-3/4" x 16" DROPPED LVL
3 PLY 1-3/4" x 14" FLUSH LVL
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
3 PLY 1-3/4" x 11-7/8" LVL HDR.
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
3 PLY 1-3/4" x 16" DROPPED LVL
3 PLY 1-3/4" x 14" FLUSH LVL
3 PLY 1-3/4" x 24" FLUSH LVL
2 PLY 1-3/4" x 14" FLUSH LVL
2 PLY 1-3/4" x 14" LVL
2 PLY 1-3/4" x 14" FLUSH LVL
3 PLY 1-3/4" x 11-7/8" DROPPED LVL
3 PLY 1-3/4" x 11-7/8" LVL HDR.
3 PLY 1-3/4" x 9-1/4" LVL HDR.